

MUNICIPAL CORPORATION, BHILAI ZONE 05 DIST-DURG
NIT
AS PER P.W.D building SOR W.E.F 01.01.2015.
PLACE OF WORK- PAVER BLOCK C/3 GARDEN SECTOR-09 HOSPITAL SECTOR WARD NO 68.

S.NO.	ITEM	QTY	UNIT
1	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits.	34	Cum
2	Providing & laying 60mm thick precast interlocking concrete blocks of approved size (approx 305 sqcm) and shape/ pattern, over 40 mm thick average complete coarse sand bed with joints of 3mm thick filled by fine sand including leveling with surface vibrator, temping and sweeping etc. complete of minimum compressive strength of 250 kg/sq.cm <b>Pigment Coloured (rubber mould) precast interlock concrete blocks</b>	340	SQM

  
 EXECUTIVE ENGINEER  
 MUNICIPAL CORPORATION,  
 BHILAI

  
 ASSISTENT ENGINEER  
 MUNICIPAL CORPORATION,  
 BHILAI

  
 SUB ENGINEER  
 MUNICIPAL CORPORATION,  
 BHILAI