

MUNICIPAL CORPORATION, BHILAI ZONE 05 DIST-DURG


NIT


AS PER P.W.D building SOR W.E.F 01.01.2015. & Electrical SOR 2015

PLACE OF WORK- वार्ड क्र. 57 सेक्टर 06 पश्चिम सड़क 34 में विद्युत एवं मंच का संधारण कार्य।

S.NO.	ITEM	QTY	UNIT
1	15 mm thick Table rubbed polished Granite stone slab flooring laid over 20mm (Average) thick base of cement mortar 1:4 (1 cement : 4 coarse sand) laid and jointed with grey cement slurry including rubbing and polishing etc. complete. (Area of slab should be 0.50 sqm and above)	102.5	SQM
2	Wiring for circuit/ sub main wiring along with earth wire with the following sizes of FR PVC insulated copper conductor, single core cable in concealed steel conduit as required. 9 X 2.5 sq. mm in 32mm conduit	100	RM
3	Supplying, installation, testing and commissioning of following 230/250 volts metal halide wide beam flood light luminaries with weather proof gear box, igniter, capacitor with IP 66 protection on wall surface/ building parapet/ pole bracket complete but without lamp as required. 1x250 watt	8	EACH


EXECUTIVE ENGINEER
MUNICIPAL CORPORATION,
BHILAI


ASSISTENT ENGINEER
MUNICIPAL CORPORATION,
BHILAI


SUB ENGINEER
MUNICIPAL CORPORATION,
BHILAI