

**MUNICIPAL CORPORATION OF BHILAI
NIT**

कार्य का नाम :-वार्ड 24 एवं 25 में सार्वजनिक शौचालय का संधारण कार्य।

(As Per PWD Building SOR 01.01.2015 & Electric SOR 01.07.2015)

PARTICULERS OF ITEMS

		Quantity	UOM
	Providing, laying and jointing glazed stoneware pipes grade 'A' with stiff mixture of cement mortar in the proportion of 1:1 (1 cement : 1 fine sand) including testing of joints etc. complete : 100 mm diameter	30.00	Mtr
2	Providing and constructing brick masonry road gully chamber 50x45x60cm with well burnt modular clay bricks crushing strength not less than 35kg/cm ² in cement mortar 1:4 (1 cement : 4 coarse sand) including 500 x 450 mm precast R.C.C. horizontal grating with frame complete as per standard design.	6	No.
3	Cement concrete flooring with cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20mm) finished with a floating coat of neat cement.40 mm thick	24.00	Sqm
4	Providing and laying cement concrete 1:5:10 (1 cement : 5 coarse sand : 10 graded stone aggregate 40 mm nominal size) all-round S.W. pipes including bed concrete 150mm thick as per standard design:100 mm diameter S.W. pipe	18.00	Mtr
5	Steel work welded in built up sections/ framed work including cutting, hoisting, fixing in position and applying a priming coat of red oxide zinc chromate primer.In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works.	60.00	Kg
6	Providing and fixing steel door made of angle iron of suitable sizes with M.S. grill of approved pattern made of M.S. flats or square or round bars coat of red oxide zinc chromate primer.	30.00	Kg
7	Providing and fixing sliding shutter with M.S. sheet 1mm thick, frame and diagonal braces of 40x40x6mm angle iron, 3.0 mm thick M.S. gusset plates at junctions and corners, 25mm dia pulley, 40x40x6mm angle and T-iron guide at top and bottom respectively including applying a priming coat of red oxide zinc chromate primer.	30.00	Kg
8	Providing and fixing on wall face or under floor UV stabilized Unplasticised Rigid PVC pipes (single socketed) having 3.2mm wall thickness conforming to IS : 13592 (4kg/sqcm) including required couplers, jointing with seal ring conforming to IS : 5382 leaving 10 mm gap for thermal expansion etc complete. 110 mm dia	30.00	Mtr
9	Providing and fixing on wall face or under floor UV stabilized Unplasticised Rigid PVC pipes (single socketed) having 3.2mm wall thickness conforming to IS : 13592 (4kg/sqcm) including required couplers, jointing with seal ring conforming to IS : 5382 leaving 10 mm gap for thermal expansion etc complete. 150 mm dia	30.00	Mtr
10	Neat Cement punning.	18.00	Sqm
11	Dismantling terrazzo or mosaic or glazed vitreous or patent cement or tiled flooring or dado skirting of any thickness without sub base.	52.20	Sqm
12	Demolishing brick masonry including arches, stacking of serviceable material disposal of unserviceable material within 50 metres lead. In cement mortar.	2.02	Cum
13	Dismantling doors chowkhats with shutters (steel or wood) including architrave, hold fast etc. complete and stacking within 50 metres lead.	12	Each
14	Providing and making 6mm thick cement plaster of mix: In Cement mortar 1:3 (1 cement : 3 fine sand)	25.20	Sqm
15	Providing and making 15mm thick cement plaster on the rough side of single or half brick wall of mix:In Cement Mortar 1:5 (1 cement : 5 fine sand)	37.80	Sqm
16	Providing and making 12mm thick cement plaster of mix: In Cement Mortar 1:4 (1 cement : 4 fine sand)	37.80	Sqm
17	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).	1.62	Cum

S.N.	PARTICULARS OF ITEMS	Quantity	
18	Providing and fixing 30mm thick fibreglass reinforced plastic (F.R.P.) flush door shutter in different plain and wood finish made with fire retardant grade unsaturated polyester resin, moulded to 3mm thick FRP laminate all around, with suitable wooden blocks inside at required places for fixing of fittings and polyurethane foam (PUF) / Polystyrene foam to be used as filler material throughout the hollow panel, casted monolithically with testing parameters of F.R.P. laminate conforming to table - 3 of IS: 14856 : 2000, complete.	10.80	Cum
19	Providing and constructing soak pit 1.20x1.20x1.20m filled with brickbats including S.W. drain pipe 100 mm diameter and 1.20 m long complete as per standard design.	6	Each
20	Brick work with modular fly-ash lime bricks (FaLG Bricks) conforming to IS:12894-2002 of class designation 4.0 in foundation and plinth in: Cement Mortar 1:6 (1 cement : 6 coarse sand)	1.20	Cum
21	Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size). Extra for precast PCC/ RCC work of any mix including form work, hoisting and fixing in Cement Mortar. 1:2 (1 Cement : 2 coarse sand) and finishing with cement plaster in Cement Mortar 1:3 (1 Cement : 3 coarse sand) but excluding reinforcement.	0.81	Cum
22	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.	2.37	Cum
23	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire in foundation and plinth all complete: Thermo-Mechanically treated bars FE 415	40.50	Kg
24	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 40mm nominal size).	1.08	Cum
25	Providing and laying vitrified floor tiles with soluble salt printing, of size 600x600mm with water absorption less than 0.5% and conforming to IS : 15622 of approved make, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand) including grouting the joints with white cement and matching pigments etc. complete.	12.00	Sqm
26	Providing and laying ceramic glazed floor tiles conforming to IS : 15622 of approved size, make, colour, shade laid on 20 mm thick Cement Mortar 1:4 (1 cement : 4 coarse sand) including pointing the joints with white cement mixed with matching pigment etc., complete. Size 300x300mm	5.40	Sqm
27	Providing and fixing ceramic glazed wall tiles conforming to IS : 15622 of approved make, colours, shades and --- 12 mm thick bed of cement Mortar 1:3 -----cement slurry @ 3.3kg per sqm including pointing in white cement mixed with matching pigment complete. Size upto 200x300mm	3.00	Sqm
28	Providing and applying plaster of paris putty over plastered wall surface including scaffolding complete More than 2 mm thickness to make surface even and smooth in true plumb and line and level.	18.00	Sqm
29	Distempering with acrylic washable distemper to give an even shade. On new work (Two or more coats)	18.00	Sqm
30	Distempering with acrylic washable distemper to give an even shade On old work (one or more coats)	25.20	Sqm
31	Painting exterior surface with PREMIUM ACRYLIC SMOOTH exterior paint of required shade as per manufacturer's specifications to give protective and decorative finish including cleaning washing of surface etc. complete with: On old work (One or more coats applied @ 0.83 ltr/ 10 sqm)	54.00	Sqm
32	Painting exterior surface with PREMIUM ACRYLIC SMOOTH exterior paint of required shade as per manufacturer's specifications to give protective and decorative finish including cleaning washing of surface etc. complete with: On new work (Two or more coats applied @ 1.43 ltr/ 10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/ 10 sqm)	21.60	Sqm
33	Providing and fixing 10 litre capacity P.V.C. low level flushing cistern conforming to IS : 7231, with all fittings and fixtures complete. White	12	Each
34	Painting on old work (two or more coats) to give an even shade with: Satin synthetic enamel paint	34.65	Sqm

PARTICULERS OF ITEMS

		Quantity	UOM
	Providing and fixing flexible P.V.C. waste pipe for sink or wash basin including P.V.C. waste fittings complete. 32 mm dia		
	Providing and fixing water closet squatting pan (Indian type W.C. pan), 100mm sand cast Iron P or S trap, 10 litre low level P.V.C. flushing cistern (same colour) conforming to IS : 7231, with flush bend and other fittings and fixtures complete including cutting and making good the walls and floors wherever required : White Orissa pattern W.C. pan of size 580x440 mm	12	Each
37	Providing and fixing vitreous china water closet (European type W.C. pan) with white ISI marked plastic seat and lid, 10 litre low level white P.V.C. flushing cistern (same colour), conforming to IS : 7231, with all fittings and fixtures complete including cutting and making good the walls and floors wherever required : White pedestal type	6	Each
38	Providing and fixing vitreous china wash basin with C.I. brackets, 32mm C.P. brass waste of standard pattern, including painting of brackets, cutting and making good the walls wherever required : White Size 550x450 mm	8	Each
39	Towel rail (600mm long x 20mm dia)	12	Each
40	Chequered precast cement concrete tiles 22mm thick in footpath & courtyard jointed with neat cement slurry mixed with pigment to match the shade of tile including cleaning of joint etc complete on 20 mm thick bed of cement mortar 1:4 (1 cement :4 coarse sand) :Ordinary cement without any pigment	12	Each
41	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings i/c fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and the cost of cutting chases and making good the same including testing of joints complete as per direction of Engineer in Charge. 15 mm nominal outer dia .Pipes.	13.50	Sqm
42	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings i/c fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and the cost of cutting chases and making good the same including testing of joints complete as per direction of Engineer in Charge. 25 mm nominal outer dia .Pipes.	30	Mtr
43	Providing and placing on terrace (at all levels) polyethylene water storage tank ISI marked with cover and suitable locking arrangement and ---- holes for inlet, outlet and overflow pipes but without fittings and the base support for tank.	30	Mtr
44	Providing and laying in trenches G.I. pipes medium class complete with G.I. fittings including excavation of trenches, refilling the same and testing of joints complete: 25 mm dia. nominal bore	500	Ltr
45	Providing and laying in trenches G.I. pipes medium class complete with G.I. fittings including excavation of trenches, refilling the same and testing of joints complete: 15 mm dia. nominal bore	20.00	Mtr
46	Providing and fixing on wall surface G.I. pipes medium class complete with G.I. fittings and clamps, including cutting, making good the walls etc. and testing of joints complete: 25 mm dia. nominal bore	20.00	Mtr
47	Providing and fixing gun metal gate valve with C.I. wheel of approved quality (screwed end): 25 mm nominal bore	30.00	Mtr
48	Providing and fixing 15 mm nominal bore Brass bib/stop cock of approved quality: Bib cock (250 grams)	6	No
49	Electrification Work As electric SOR 01.07.2015 Lum-Sum	24	No
			₹25000.00

कार्यपालन अभियन्ता
नगर पालिक निगम, भिलाई

सहायक अभियन्ता
नगर पालिक निगम, भिलाई

उप अभियन्ता
नगर पालिक निगम, भिलाई