

OFFICE OF THE MUNICIPAL CORPORATION BHILAI ZONE-05. DIST:-DURG.

NIT

NAME OF WORK :- वार्ड क्र. 53 सेक्टर 57 में सड़क 01 के सामने नाली संघारण कार्य।


| S.NO | ITEM | QTY | PER |
|------|--|--------|-----|
| 1 | Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits. In all types of soil | 39.20 | cum |
| 2 | Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size). | 5.6 | cum |
| 3 | Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size). | 14.00 | cum |
| 4 | Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire in foundation and plinth all complete: Thermo-Mechanically treated bars | 910.00 | kg |
| 5 | Providing and fixing form work including centring, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for: Foundations, footings, bases of columns plinth beam, curtain wall in any shape and size and all type of wall below plinth level. | 112.00 | sqm |
| 6 | Carriage by mechanical transport upto 5 km lead: | 54.00 | sqm |



EXECUTIVE ENGINEER
MUNICIPAL CORPORATION
BHILAI



ASSISTANT ENGINEER
MUNICIPAL CORPORATION
BHILAI



SUB ENGINEER
MUNICIPAL CORPORATION
BHILAI