

MUNICIPAL CORPORATION BHILAI (C.G.)

NIT

Name of work :- वार्ड क्र . 53 सेक्टर 05 सड़क 01 में मार्ग संधारण कार्य


S.No.	Description and details of work	Qty.	unit
1	Excavation in Soil (by Manual Means.) Excavation for roadway in soil using including loading in tipper for carrying of cut earth to embankment site and unloading with all lifts and lead upto 1000 meters as per relevant clauses of section 300.	22.75	cum
2	Providing and laying cement concrete for plain concrete/ reinforced concrete i/c form work, shuttering complete in as per drawings and specifications. P.C.C. M-30	34.125	cum
1	Construction of Shoulders (Construction of shoulders as per clause 408 with selected soil from borrow pits / borrow areas having CBR not less than 12 and shall have L.L. and P.I. not more than 25% and 6% respectively, inclusive of all leads and lifts, including clearing and scrapping of existing surface, providing required cross fall, compacting. watering rolling and royalty charges etc. complete. With smooth wheeled roller	9.75	cum



EXECUTIVE ENGINEER
MUNICIPAL CORPORATION
BHILAI



ASSISTANT ENGINEER
MUNICIPAL CORPORATION
BHILAI



SUB ENGINEER
MUNICIPAL CORPORATION
BHILAI