

# MUNICIPAL CORPORATION BHILAI (C.G.)

## NIT


कार्य का नाम :- वार्ड-08 स्थित देवांगन समाज जनसेवा समिति के पास मंच निर्माण कार्य।


Pwd Building Sor 01.01.2015


S. No.	Description and details of work	Qty.	Unit
1	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits. In all types of soil	15.12	Cum
2	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).	5.97	Cum
3	Providing and laying mech. Mixed reinforced cement concrete e/x centering, shuttering and reinforcement in foundation, plinth and in superstructure up to a height of 4.0m. above plinth level. 1:1/1.5:3	8.78	Cum
4	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire all complete: Thermo-Mechanically treated bars	878.00	Kg
5	Providing and fixing formwork including centering, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for:		
	(A) Foundations, footings, base of columns and plinth beam in any shape and size.	19.14	Sqm
	(B) Columns, Pillars, Piers and likes- rectangular or square in shape	17.82	Sqm
	(C) Suspended floors, roofs, access platform, balconies (plain surfaces) and shelves (cast in situ)	41.44	Sqm
6	Brick work with modular fly-ash lime bricks (FALG Bricks) confirming to IS:12894-2002 of class designation 40 in foundation and plinth in :Cement Mortar 1:6	4.56	Cum
7	Providing and filling in plinth with sand/Crusher dust and hard moorum under floor, including ----- cost of all labour, materials, T & P etc. complete required for the work.	22.95	Cum
9	Providing and laying damp proof course (upto 50mm thick) with plain cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded crushed stone aggregate 20mm nominal size) including form work.	0.29	Cum
10	Brick work with modular well burnt (open bhatta) clay bricks of crushing strength not less than 20 kg/sqcm and water absorption not more than 25% in foundation and plinth in: Extra for brick work in superstructure above plinth level for every floor or part thereof in addition to rate for foundation and plinth:	5.76	Cum
11	Providing and making 6mm thick cement plaster of mix: In Cement mortar 1:4 (1 cement : 4 fine sand)	73.86	Sqm



S.No.	Description and details of work	Qty.	Unit
12	Providing and making 15mm thick cement plaster on the rough side of single or half brick wall of mix: In Cement Mortar 1:6 (1 cement : 6 fine sand)	107.92	Sqm
14	Cement concrete flooring with cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20mm) finished with a floating coat of neat cement. 40 mm thick	25.80	Sqm
15	Finishing walls with water proofin cement paint to give an even shade. On new Work	181.78	Sqm
16	Distemping with acrylic washable distemper to give an even shade. On new work (Two or more coats)	85.97	Sqm

  
**Executive Engineer**  
**Municipal Corporation**  
**Bhilai (C.G)**

  
**Asstt. Engineer**  
**Municipal Corporation**  
**Bhilai (C.G)**

  
**Sub. Engineer**  
**Municipal Corporatio**  
**Bhilai (C.G)**