

16


MUNICIPAL CORPORATION BHILAI


NIT


वार्ड क्र. 23 पुलिस लाईन में 03 लाईन शेष का सीमेन्टीकरण कार्य।

(As Per PWD Building & Road SOR works w.e.f 01/01/2015 & NON Sor Item)

| SN. | Details of Item | Qty. | Unit |
|-----|---|--------|----------------|
| 1 | Providing and laying cement concrete for plain concrete/ reinforced concrete i/c form work, shuttering complete in as per drawings and specifications.(For Village roads) P.C.C. M-10 | 27.50 | m ³ |
| 2 | Providing and laying cement concrete for plain concrete/ reinforced concrete i/c form work, shuttering complete in as per drawings and specifications.(For Village roads) P.C.C. M-30 | 105.00 | m ³ |
| 3 | Providing and laying cement concrete for plain concrete/ reinforced concrete i/c form work, shuttering complete in as per drawings and specifications.(For Village roads) P.C.C. M-25 | 93.75 | m ³ |
| 4 | Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete. | 156.00 | m ³ |
| 5 | <u>Non Sor Item</u> Cutting & Filling with bitumen in expansion joints of CC Road per CM depth & per CM width. | 400.00 | Rm |


सहायक अभियन्ता
नगर पालिक निगम, भिलाई


ज.प. अभियन्ता
नगर पालिक निगम, भिलाई


कार्यपालक अभियन्ता
नगर पालिक निगम, भिलाई