

MUNICIPAL CORPORATION BHILAI (C.G.)

NIT

Name of work :- वार्ड क्र. 64 सेक्टर 10 सड़क 30 एवं 32 के गध्य बोर खनन कार्य।

| Sl. No. | ITEM | Qty. | UNIT |
|---------|--|------|-------|
| 1 | 21.1 Boring/drilling bore well perfectly vertical for the specified depth suitable to receive required dia for casing/ strainer pipe, by suitable method prescribed in IS: 2800 (part I), including collecting samples from different strata, preparing and submitting strata chart/bore log, including hire & running charges of all equipments, tools, plants & machineries required for the job, all complete as per direction of Engineer-in-charge upto 90 metre depth below ground level. 21.1.1.3 150 mm dia. | 39 | m |
| 2 | 21.1.2 Rocky strata including Boulders 21.1.2.3 150 mm dia. | 50 | m |
| 3 | 21.5 Supplying, assembling, lowering and fixing in vertical position in bore well, ISI marked G.I. casing pipe (Plain) medium class in 4 to 7 meters length one end fitted with socket as per IS: 1239 (Part-1&Part-2) 1992 with IVth revision (Up-to-date amendments), of reputed & approved make, including required hire & labour charges, fittings & accessories, all complete, for all depths, as per direction of Engineer-in-charge. 21.5.3 150 mm nominal dia | 39 | m |
| 4 | 21.16 Providing ISI Mark 32 mm dia G.I. (B class) riser pipe and M.S. plunger rod in 3 meter length socketed on one end as per IS: 1239 (Part I) 1990 with up to date amendments and socket as per IS: 2062/1990 up to date amendments. | 25 | m |
| 5 | 1.18 Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete. | 0.72 | cum |
| 6 | 3.1 Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work 3.1.2 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size). | 0.12 | cum |
| 7 | 3.1 Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work 3.1.5 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size). | 0.36 | cum |
| 8 | 7.5 Brick work with modular fly-ash lime bricks (FaLG Bricks) conforming to IS:12894-2002 of class designation 4.0 in foundation and plinth in 1:1:6 | 0.12 | cum |
| 9 | 21.15 Providing and placing in position India Mark II hand pump with 32 mm diameter riser pipe assembly complete with all accessories (riser pipe and plunger rod to be paid separately | 1 | point |


EXECUTIVE ENGINEER
MUNICIPAL CORPORATION
BHILAI


ASSISTANT ENGINEER
MUNICIPAL CORPORATION
BHILAI


SUB ENGINEER
MUNICIPAL CORPORATION
BHILAI