MUNICIPAL CORPORATION BHILAI (C.G.) NIT

कार्य का नाम :- वार्ड-12 सुपेला कान्ट्रेक्टर कालोनी बजंगर चौक में पेवर ब्लाक एवं संधारण कार्य।

Pwd Building Sor 01.01.2015

S.No.	Description and details of work	Qty.	Unit
1,	Providing & laying 60mm thick precast interlocking concrete blocks of approved size (approx 305 sqcm) and shape/ pattern, over 40 mm thick average complete coarse sand bed with joints of 3mm thick filled by fine sand including leveling with surface vibrator, temping and sweeping etc. complete of minimum compressive strength of 250 kg/sq.cm Pigment Coloured (rubber mould) precast interlock concrete blocks	374.00	Sqm
2	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	14.96	Sqm

Executive Engineer Municipal Corporation Bhilai (C.G) Asstt. Engineer
Municipal Corporation
Bhilai (C.G)

Sub. Engineer Municipal Corporatio Bhilai (C.G)