

OFFICE OF THE MUNICIPAL CORPORATION BHILAI ZONE-05. DIST:-DURG.

NIT

NAME OF WORK :- *वि. प्र. 05 (हॉल-05) पार्क प 2155 में अंतर्गत काम (हॉल-05)*

S.NO	ITEM	QTY	PER
1	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits. In all types of soil	0.75	cum
2	Providing and fixing form work including centring, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for: Foundations, footings, bases of columns plinth beam, curtain wall in any shape and size and all type of wall below plinth level.	6	sqm
3	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 40mm nominal size).	1.5	cum
4	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.	4.8	cum
5	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).	4.8	cum
6	Providing & laying 60mm thick precast interlocking concrete blocks of approved size (approx 305 sqcm) and shape/ pattern, over 40 mm thick average complete coarse sand bed with joints of 3mm thick filled by fine sand including leveling with surface vibrator, temping and sweeping etc. complete of minimum compressive strength of 250 kg/sq.cm Pigment Coloured (rubber mould) precast interlock concrete blocks	4.8	cum
7	Brick work with modular well burnt (open bhatta) clay bricks of crushing strength not less than 20 kg/sqcm and water absorption not more than 25% in foundation and plinth in:Cement Mortar 1:6 (1 Cement : 6 Coarse Sand)	5.4	cum
8	Structural steel work in single section including cutting, hoisting, fixing in position and applying a priming coat of red oxide zinc chromate primer.	1500	kg
9	Providing and laying ceramic glazed floor tiles conforming to IS : 15622 of approved size, make, colour, shade laid on 20 mm thick Cement Mortar 1:4 (1 cement : 4 coarse sand) including pointing the joints with white cement mixed with matching pigment etc., complete. 12.9.1 Size 300x300mm	48	sqm

10	Supply and fixing of precoated galvanized iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-charge) 0.50 mm +/- 5% total coated thickness (TCT), Zinc coating 120gsm as per IS: 277 in 240mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches while transportation and should be supplied in single length upto 12 metre or as desired by Engineer-in-charge.	70	sqm
11	Providing and fixing ceramic glazed wall tiles conforming to IS : 15622 of approved make, colours, shades and size on wall and dados over 12 mm thick bed of cement Mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm including pointing in white cement mixed with matching pigment complete. Size upto 200x300mm	16.8	sqm


EXECUTIVE ENGINEER
MUNICIPAL CORPORATION
BHILAI


ASSISTANT ENGINEER
MUNICIPAL CORPORATION
BHILAI


SUB ENGINEER
MUNICIPAL CORPORATION
BHILAI