MUNICIPAL CORPORATION BHILAI (C.G.)

NIT

कार्य का नाम :-- पार्षद निधि से वार्ड-08 में स्थित सियान सदन में टाईल्स लगाने का कार्य।

Pwd Building Sor 01.01.2015

S.No.	Description and details of work	Qty.	Unit
1	Providing and laying vitrified floor tiles with soluble salt printing, of size 600x600mm with water absorption less than 0.5% and conforming to IS: 15622 of approved make, laid on 20mm thick cement mortar 1:4 (1 cement: 4 coarse sand) including grouting the joints with white cement and matching pigments etc. complete.	84.00	Sqm
2	Cement concrete flooring with cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20mm) finished with a floating coat of neat cement. 40 mm thick	84.00	Sqm

Executive Engineer Municipal Corporation Bhilai (C.G) Assit. Engineer Municipal Corporation Bhilai (C.G) Sub. Engineer Municipal Corporatio Bhilai (C.G)