

MUNICIPAL CORPORATION BHILAI (C.G.)

NIT

कार्य का नाम :- पार्षद निधि से वार्ड-05 दुर्गा पास में भवन संधारण कार्य।


भीमनगर

Pwd Building Sor 01.01.2015

S.No.	Description and details of work	Qty.	Unit
1	Cement concrete flooring with cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20mm) finished with a floating coat of neat cement. 50 mm thick	146.40	Sqm
2	Repairs to plaster in patches of area 2.5 sq. metres and under including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls with cement mortar 1:4 (1 cement : 4 fine sand) complete including disposal of rubbish to the dumping ground within 50metres lead : Thickness more than 15mm and upto 20mm	154.00	Sqm
3	Wall painting with acrylic luxury emulsion (plastic) paint of required shade to give an even shade. On old work (one or more coats)	200.00	Sqm
4	On new work (Two or more coats applied @ 1.43 ltr/ 10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/ 10 sqm) On old work (One or more coats applied @ 0.83 ltr/ 10 sqm)	150.00	Cum
5	Providing and applying 2mm thick ready mix exterior grade approved make putty (like Birla wall care, Alltek Superfine W/R of (NCL), Asian, ICI, Nerolac, J.K. wall putty) on walls to make the surface smooth and even.	200.00	Sqm
6	Painting on new work (two or more coats) to give an even shade with: Satin synthetic enamel paint	7.44	Sqm
7	10% For Electrification	9079.60	Rs



Executive Engineer
Municipal Corporation
Bhilai (C.G)



Asstt. Engineer
Municipal Corporation
Bhilai (C.G)



Sub. Engineer
Municipal Corporatio
Bhilai (C.G)