MUNICIPAL CORPORATION BHILAI (C.G.)

NIT

कार्य का नाम :- जोन-01 क्षेत्रांतर्गत एम.डी.पी.ई. पाईप लाईन बिछाने एवं घर घर नल कनेक्शन कार्य।

NON SOR ITEM

S.No.	Description and details of work	Qty.	Unit
1	Providing & Laying MDPE Blue Pipe Line including Excavation of trenches, refilling the same all fitting & testing of joints etc. complete		
	63 mm dia	300.00	Metre
	75 mm dia	100.00	Metre
	110 mm dia	150.00	Metre
2	Providing domestic house connection by making hole to distribution line (D.I. or MDPE) of any diameter by suitable mechanical machine by fixing of strap saddle i/e other required accessories with jointing 20 mm OD MDPE main pipe upto 3.00 meter avarage (1.00 meter to 5.00 meter) as per PE-80PN-16/,ISO 4427-2007 in case to the connection of MDPE main pipe PP or electro fusion service saddle as per BSEN 12201/3 standard to be used with accessories such metal inserted female threaded adapter (SS304) standard in this work excavation, drilling,refilling,road cutting and trap clamping if neccessary will be done and other allied work will br be included (completion certificate of connection from the beneficiary will be submitted by the agency.) i/e retro rotion work.	400.00	Job

Executive Engineer Municipal Corporation Bhilai (C.G) Asstt. Engineer
Municipal Corporation
Bhilai (C.G)

Sub. Engineer Municipal Corporatio Bhilai (C.G)