

# MUNICIPAL CORPORATION OF BHILAI

NIT

वार्ड क्र. 49 सेक्टर 02 सड़क 06 में उद्यान निर्माण कार्य।

As Per PWD Building/Road SOR 01.01.2015, & NON SOR ITEM

S.N.	PARTICULERS OF ITEMS	Quantity	UOM
1	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits. In all types of soil	62.26	Cum
2	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).	20.96	Cum
3	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	13.20	Cum
4	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.	118.61	Cum
5	Providing & laying 60mm thick precast interlocking concrete blocks of approved size (approx 305 sqcm) and shape/ pattern, over 40 mm thick average complete coarse sand bed with joints of 3mm thick filled by fine sand including leveling with surface vibrator, temping and sweeping etc. complete of minimum compressive strength of 250 kg/sq.cm Plain/ normal coloured precast interlock concrete blocks	80.00	Sqm
6	Surface dressing of the ground including removing vegetation and making up undulations and inequalities not exceeding 15 cms in depth/ height including disposal of rubbish upto 1.5 m lift and lead upto 50m (at least 5m away from the dressed area).	200.00	Sqm
7	Supplying and stacking of good earth at site including royalty, loading, unloading and carriage upto 5 km (earth measured in stacks will be reduced by 20% for payment).	12.00	Cum
8	Supplying and stacking at site well decayed cow dung manure from approved source, including loading, unloading and carriage upto 5 km (manure measured in stacks will be reduced by 8% for payment).	10.00	Cum
9	Spreading of sludge, dump manure or/and good earth in required thickness (Cost of sludge, dump manure or/ and good earth to be paid separately).	80.00	Cum
10	Providing and planting following herbs in garden including preparation of soil, base plantation, providing and spreading different fertilizers, soil and sand: Hedges like Alife, Dorenta, Tikoma etc	500	Each
11	Furn like Arica, China etc (3 year old)	42	Each
12	Hibiscus (Flower)/ Rose	100	Each
13	Carpet grass (well developed)	100	sqm
14	Painting exterior surface with PREMIUM ACRYLIC SMOOTH exterior paint of required shade as per manufacturer's specifications to give protective and decorative finish including cleaning washing of surface etc. complete with: On new work (Two or more coats applied @ 1.43 ltr/ 10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/ 10 sqm)	122.52	Sqm
15	Painting on new work (two or more coats) to give an even shade with: Aluminium paint	195.00	Sqm
16	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 40mm nominal size).	3.228	Cum
17	Providing and placing in position angle iron post and strut of required size including bottom to be split and bent at right angle in opposite direction for required length and drilling holes upto 10 mm dia as per requirement including priming coat with red oxide zinc chromate primer and placing the post/ strut in cement concrete block.	161.242	kg
18	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire all complete: Thermo-Mechanically treated bars	306.80	Kg

S.N.	PARTICULARS OF ITEMS	Quantity	UOM
19	Steel work welded in built up sections/ framed work including cutting, hoisting, fixing in position and applying a priming coat of red oxide zinc chromate primer. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works.	524.026	Kg
20	Providing and fixing formwork including centering, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for:(A) Foundations, footings, base of columns and plinth beam in any shape and size.	32.00	Sqm
21	Providing and fixing in position chain linked steel wire fabric made of 4 mm dia G.I. wire of required width in mesh to concrete/ wooden/ angle iron posts including securing and screwing with 2mm dia G.I. wire, G.I. staples, G.I.U-nails or steel pins etc., complete. Aperture 50x50mm	48.00	Sqm
22	Painting on new work (two or more coats) to give an even shade with: Satin synthetic enamel paint	10.30	Sqm
23	Providing and fixing form work including centering, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for: Columns, beams & walls- circular or any other geometrical shape other than square and rectangular in all sizes	7.68	Sqm
24	Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	1.47	Cum
25	Providing and making 12mm thick cement plaster of mix: In Cement Mortar 1:4 (1 cement : 4 fine sand)	5.52	Sqm
26	AS PER PWD ROAD SOR 01.01.2015 Cement art Mural work	15.00	Sqm
27	<u>NON SOR ITEM</u> Providing & Planting well developed & healthy (5' and above) orna mental plants with digging holes soil filling & chemical & biological treatment like ficus cycas chhatim, bottle palm, supari palm, musanda & avenue palm, tree including 6th month maintenance till well established as directed Engineer In charge	20	Each
28	<u>NON SOR ITEM</u> Providing & Planting well established flowering & orna mental plants or shrubs like nerium, bougainvillia, crotons, vidhya etc. with digging holes & chemical treatment including 6th month maintenance till well established as directed Engineer In charge	40	Each
29	<u>NON SOR ITEM</u> Providing & Planting well developed succulent healthy orna mental plants with digging chemical treatment like thuja, cycas, lolina etc, including 6th month maintenance till well established as directed Engineer In charge	25	Each
30	<u>NON SOR ITEM</u> Providing & fixing of Steel Bench Area 1.20x0.70 m Height 0.45 m above level seating ----- proper grip fixing with 1:2:4 Cement Concrete	2	Each
31	<u>NON SOR ITEM</u> Providing & fixing of Double Swing Jhula	1	Each

कार्यपालक अभियन्ता  
नगर पालिक निगम, मिलालाई

सहायक अभियन्ता  
नगर पालिक निगम, मिलालाई

उप अभियन्ता  
नगर पालिक निगम, मिलालाई