



MUNICIPAL CORPORATION BHILAI
NIT

कार्य का नाम:- वार्ड क्रमांक 25 के विभिन्न स्थानों पर सीमेंटीकरण कार्य।

(As Per PWD Building & Road SOR works w.e.f 01/01/2015 & NON Sor Item)

SN	Details of Item	Qty.	Unit
1	Providing and laying cement concrete for plain concrete/ reinforced concrete i/c form work, shuttering complete in as per drawings and specifications. (For Village roads) P.C.C. M-10	28.00	Cum
2	Providing and laying cement concrete for plain concrete/ reinforced concrete i/c form work, shuttering complete in as per drawings and specifications. (For Village roads) P.C.C. M-30	131.25	Cum
3	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	75.00	Cum
4	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.	117.00	Cum
5	<u>Non Sor Item</u> (Fix rate) Cutting & Filling with bitumen in expansion joints of CC Road per CM depth & per CM width.	100.00	Rm


कार्यपालक अभियन्ता
नगर पालिक निगम, भिलाई


सहायक अभियन्ता
नगर पालिक निगम, भिलाई


उप अभियन्ता
नगर पालिक निगम, भिलाई