

MUNICIPAL CORPORATION OF BHILAI

NIT


कार्य का नाम:-वार्ड क्रमांक 23 पुरानी गछली मार्केट भवन का जीर्णोद्धार


(As Per PWD Building SOR 01.01.2015 & Electric SOR 01.07.2015)


S.N.	PARTICULARS OF ITEMS	Quantity	UOM
1	Demolishing brick masonry including arches, stacking of serviceable material disposal of unserviceable material within 50 metres lead. In cement mortar.	12.54	cum
2	Demolishing R.C.C. work including stacking of steel bars and disposal of unserviceable material within 50 metre lead.	1.70	Cum
3	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits. In all types of soils.	28.58	Cum
4	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).	3.37	Cum
5	Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	15.798	Cum
6	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire all complete: Thermo-Mechanically treated bars	1579.8	Kg
7	Providing and fixing form work including centring, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for: Foundations, footings, bases of columns plinth beam, curtain wall in any shape and size and all type of wall below plinth level.	24.12	Sqm
8	Providing and fixing form work including centring, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for: Columns, Pillars, Piers and likes- rectangular or square in shape	26.40	Sqm
9	Providing and fixing form work including centring, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for: Beams, lintels, cantilevers & walls	7.04	Sqm
10	Providing and fixing form work including centring, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for: Suspended floors, roofs, access platform, balconies (plain surfaces) and shelves (cast in situ)	53.24	Sqm
11	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.	15.00	Cum
12	Brick work with modular fly-ash lime bricks (FaLG Bricks) confirming to IS:12894-2002 of class designation 4.0 in foundation and plinth in: Cement Mortar 1:6 (1 cement : 6 coarse sand)	1.76	Cum
13	Brick work with modular fly-ash lime bricks (FaLG Bricks) confirming to IS:12894-2002 of class designation 4.0 in foundation and plinth in: Cement Mortar 1:6 (1 cement : 6 coarse sand) Extra for brick work in superstructure above plinth level for every floor or part thereof in addition to rate for foundation and plinth:	9.83	Cum
14	Providing and making 6mm thick cement plaster of mix: In Cement mortar 1:3 (1 cement : 3 fine sand)	38.08	Sqm
15	Providing and making 12mm thick cement plaster of mix: In Cement mortar 1:4 (1 cement : 4 fine sand)	51.81	Sqm

1 of 2

S.N.	PARTICULARS OF ITEMS	Quantity	UOM
16	Providing and making 15mm thick cement plaster of mix: 1:3 Cement mortar 1:5 (1 cement : 5 fine sand)	78.00	Sqm
17	Providing and fixing steel door/window with M.S. sheet 1mm thick, frame of angle iron, diagonal braces of angle for top of suitable size, 3.00 mm M.S. gusset plates in junction and corners, all necessary fittings complete including applying a priming coat of red oxide zinc chromate primer.	243.00	Kg
18	Providing and fixing M.S. grill of approved pattern made of M.S. plate or square or round bars welded to steel frame of window etc. including applying a priming coat welded in frame with all necessary fitting complete including applying a priming of red oxide zinc chromate primer.	200.1	Kg
19	Providing and laying vitrified floor tiles with soluble salt priming, of size 600x600mm with water absorption less than 0.5% and conforming to IS : 15622 of approved make, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand) including grouting the joints with white cement and matching pigments etc., complete.	123.04	Sqm
20	Providing and laying ceramic glazed floor tiles conforming to IS : 15622 of approved size, make, colour, shade laid on 20 mm thick Cement Mortar 1:4 (1 cement : 4 coarse sand) including pointing the joints with white cement mixed with matching pigment etc., complete size 300x300mm	27.04	Sqm
21	Providing and applying plaster of paris putty over plastered wall surface including scaffolding complete. More than 2 mm thickness to make surface even and smooth in true plumb and line and level.	167.89	Sqm
22	Painting exterior surface with PREMIUM ACRYLIC SMOOTH exterior paint of required shade as per manufacturer's specifications to give protective and decorative finish including cleaning washing of surface etc. complete with: On new work (Two or more coats applied @ 1.45 lit/ 10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/ 10 sqm)	78.00	Sqm
23	Wall painting with acrylic luxury emulsion (plastic) paint of required shade to give an even shade. On new work (two or more coats)	89.89	Sqm
24	Painting on new work (two or more coats) to give an even shade with: Satin synthetic enamel paint	17.01	Sqm


 कार्यपालक अभियन्ता
 नगर पालिक निगम, मिलाई


 सहायक अभियन्ता
 नगर पालिक निगम, मिलाई


 उप अभियन्ता
 नगर पालिक निगम, मिलाई