


MUNICIPAL CORPORATION BHILAI


NIT


कार्य का नाम- वार्ड क्रमांक 20 नेहरू चौक से जलेबी चौक तक सीमेंटीकरण कार्य

(As Per PWD Building & Road SOR works w.e.f 01/01/2015 & NON Sor Item)

| SN | Details of Item | Qty. | Unit |
|----|---|--------|------|
| 1 | Providing and laying cement concrete for plain concrete/ reinforced concrete i/c form work, shuttering complete in as per drawings and specifications (For Village roads) P.C.C M-10 | 50.00 | Cum |
| 2 | Providing and laying cement concrete for plain concrete/ reinforced concrete i/c form work, shuttering complete in as per drawings and specifications (For Village roads) P.C.C M-30 | 210.00 | Cum |
| 3 | Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size). | 131.25 | Cum |
| 4 | Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete. | 280.80 | Cum |
| 5 | <u>Non Sor Item</u> (Fix rate) Cutting & Filling with bitumen in expansion joints of OC Road per CM depth & per CM width | 500.00 | Rm |


कार्यपालक अभियन्ता
नगर पालिक निगम, भिलाई


सहायक अभियन्ता
नगर पालिक निगम, भिलाई


उप अभियन्ता
नगर पालिक निगम, भिलाई