

MUNICIPAL CORPORATION OF BHILAI

NIT


कार्य का नाम :- वार्ड क्र. 47 सेक्टर 01, फायर ब्रिगेड मैदान का सौंदर्यीकरण कार्य।

As Per PWD Building/Road SOR 01.01.2015, Electrical SOR 01.07.2015 & NON SOR ITEM

S.N.	PARTICULERS OF ITEMS	Quantity	UOM
1	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits. In all types of soil	194.191	Cum
2	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).	83.82	Cum
3	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	51.60	Cum
4	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.	236.09	Cum
5	Providing & laying 60mm thick precast interlocking concrete blocks of approved size (approx 305 sqcm) and shape/ pattern, over 40 mm thick average complete coarse sand bed with joints of 3mm thick filled by fine sand including leveling with surface vibrator, temping and sweeping etc. complete of minimum compressive strength of 250 kg/sq.cm Plain/ normal coloured precast interlock concrete blocks	321.60	Sqm
6	Surface dressing of the ground including removing vegetation and making up undulations and inequalities not exceeding 15 cms in depth/ height including disposal of rubbish upto 1.5 m lift and lead upto 50m (at least 5m away from the dressed area).	240.00	Sqm
7	Supplying and stacking of good earth at site including royalty, loading, unloading and carriage upto 5 km (earth measured in stacks will be reduced by 20% for payment).	12.00	Cum
8	Supplying and stacking at site well decayed cow dung manure from approved source, including loading, unloading and carriage upto 5 km (manure measured in stacks will be reduced by 8% for payment).	12.00	Cum
9	Spreading of sludge, dump manure or/and good earth in required thickness (Cost of sludge, dump manure or/ and good earth to be paid separately).	96.00	Cum
10	Providing and planting following herbs in garden including preparation of soil, base plantation, providing and spreading different fertilizers, soil and sand: Hedges like Alife, Dorenta, Tikoma etc	1000	Each
1	Furn like Arica, China etc (3 year old)	50	Each
2	Hibiscus (Flower)/ Rose	100	Each
3	Carpet grass (well developed)	100.00	sqm
	Painting exterior surface with PREMIUM ACRYLIC SMOOTH exterior paint of required shade as per manufacturer's specifications to give protective and decorative finish including cleaning washing of surface etc. complete with: On new work (Two or more coats applied @ 1.43 ltr/ 10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/ 10 sqm)	140.52	Sqm
	Painting on new work (two or more coats) to give an even shade with: Aluminium paint	225.00	Sqm
	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 40mm nominal size).	9.5	Cum




1 of 4



S.N.	PARTICULARS OF ITEMS	Quantity	Unit
18	Providing and placing in position angle iron post and strut of required size including bottom to be split and bent at right angle in opposite direction for required length and drilling holes upto 10 mm dia as per requirement including priming coat with red oxide zinc chromate primer and placing the post/ strut in cement concrete block.	574.62	Kg
19	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire all complete: Thermo-Mechanically treated bars	716.80	Kg
20	Steel work welded in built up sections/ framed work including cutting, hoisting, fixing in position and applying a priming coat of red oxide zinc chromate primer. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works.	1238.81	Kg
21	Providing and fixing formwork including centering, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for: Foundations, footings, base of columns and plinth beam in any shape and size.	114.00	Sqm
22	Providing and fixing in position chain linked steel wire fabric made of 4 mm dia G.I. wire of required width in mesh to concrete/ wooden/ angle iron posts including securing and screwing with 2mm dia G.I. wire, G.I. staples, G.I.U-nails or steel pins etc., complete. Aperture 50x50mm	171.00	Sqm
23	Painting on new work (two or more coats) to give an even shade with: Satin synthetic enamel paint	10.30	Sqm
24	Providing and fixing form work including centring, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for: Columns, beams & walls- circular or any other geometrical shape other than square and rectangular in all sizes	7.68	Sqm
25	Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	1.47	Cum
26	Providing and making 12mm thick cement plaster of mix: In Cement Mortar 1:4 (1 cement : 4 fine sand)	5.52	Sqm
27	Erection of steel tubular pole or rail pole in cement concrete 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40mm nominal size) foundation including excavation & refilling etc as required of 7 metre to 10 metre Item - 21.10.4	2.00	Each
28	Supply & fixing water tight terminal box made of 1.6 mm thick M S Sheet with detachable gland plate in bottom —. 4 way connector & 1 No. SPMCB inside the box for cable connection fixed to pole with 2 Nos. Clamp made from 40 x 3 mm MS flat with 2 Nos. nut bolts dully painted with 2 coat red oxide paint & 2 coat aluminum paint complete as required 30 x 20 x 15 cms Item - 21.16.2	2.00	Each
29	Supply & Making end termination with brass compression gland & aluminum lugs for following size armored aluminum conductor power cable of 1.1 KV grade as required 3 x 25 sq.mm Item - 17.23.10	5.00	Each
30	Supply & fixing & cramping suitable size & all type aluminum ferule/lugs for following size 1.1 KV grade power cable core/lead pressed with high pressure cramping tool including connection to switch gear/MCCB etc as required 25 sq.mm. Item - 17.28.4	8.00	Each
31	Supply & Fixing GI Pipe Along With wall or pole/support with 2 nos. MS clamp for protection of underground cable in approved manner including bolts & nuts or metal dash fasteners complete as required 40 mm dia Item - 16.5.2	75.00	Meter
32	Painting new steel & other metallic surface with red oxide zinc chromate primer paint complete with supply of material labour etc including preparation of surface Item - 33.14	11.80	Sqm
33	Supply and fixing following street light pole bracket on existing pole made out of 50 mm dia MS "B" class pipe welded to 300 mm long MS pole canopy of suitable dia at a angle of 102.50 including having MS triangular stiffener of size 150 X 50 X 5 mm thick, making arrangement for tightening the bracket with pole by providing suitable size heavy duty nuts and bolts in canopy, painting with one coat of approved steel primer etc. as required. Double Over Hang 1.50 metre Long Item - 21.9.6	5.00	Each
34	Painting wood steel & other metallic surface with aluminum paint complete with material & labour including preparation of surface Item - 33.15	11.80	Sqm
35	Providing & Laying Cast In situ Cement Concrete 1:3:6 graded stone aggregate 40 mm nominal size foundation including mixing with mechanical mixer compacting with vibrator finishing & currying etc complete but excluding formwork Item - 32.13	0.51	Cum

S.N.	PARTICULARS OF ITEMS	Quantity	UOM
36	Providing timber steel formwork for cement concrete work at all levels including removing of the same Item - 32.7	1.70	Cum
37	Earthing with G.I. earth pipe 4.5 m long 40 mm dia including accessories & providing masonry enclosure with cover plate having locking arrangement watering pipe etc (But without charcoal & salt) as required Item - 14.1	2.00	Set
38	Supplying and drawing following sizes of FR PVC insulated copper conductor, single core cable in the existing surface/ concealed, steel/ PVC conduit/ PVC casing capping as required. 3 x 2.50 sq.mm Item - 5.11.12	18.00	Sqm
39	Providing & Fixing porcelain rewirable fuse carriage----- as required 32 amps Item - 9.11.2	4.00	Each
40	Supplying, installation, testing and commissioning of following 230/250 volts LED street light fitting with all accessories like driver, heat sink made of die cast aluminium with IP 66 protection and 5 KV surge protection on pole bracket complete as required and furnishing 2 Yrs Guarantee certificate from manufacturer. 40-45 watt	4.00	Each
41	Supplying and laying following sizes one number PVC insulated/ XLPE, PVC sheathed, steel armoured, aluminium conductor power cable of 1.1 KV grade direct in ground including excavation, sand cushioning, protective covering and refilling the trench etc as required. 2 x 16 sq. mm 17.1.4	50.00	Meter
42	Carrying out the resistivity survey by VES method using Schlumberger configuration for locating the proper spot for drilling of tube well within the selected habitation, including photography, interpretation of resistivity data and submission of report in the desired format along with resistivity readings, necessary graph and photographs. (only successful point is payable)	1.00	Point
43	Boring/drilling bore well perfectly vertical for the specified depth suitable to receive required dia for casing/ strainer pipe, by suitable method prescribed in IS: 2800 (part I), including collecting samples from different strata, preparing and submitting strata chart/bore log, including hire & running charges of all equipments, tools, plants & machineries required for the job, all complete as per direction of Engineer-in-charge upto 90 metre depth below ground level. All types of soil. 125 mm dia.	30.00	Meter
44	Rocky strata including Boulders. 125 mm dia.	90.00	Meter
45	Supplying, assembling, lowering and fixing in vertical position in bore well, ISI marked G.I. casing pipe (Plain) medium class in 4 to 7 meters length one end fitted with socket as per IS: 1239 (Part-1&Part-2) 1992 with IVth revision (Up-to-date amendments), of reputed & approved make, including required hire & labour charges, fittings & accessories, all complete, for all depths, as per direction of Engineer- in-charge. 125 mm nominal dia.	30.00	Meter
46	Providing and fixing M.S. clamp of required dia to the top of casing/ housing pipe of tube well as per IS: 2800 (part I), including necessary bolts & nuts of required size complete. 125 mm clamp.	1.00	Each
47	Providing and fixing on wall surface G.I. pipes medium class complete with G.I. fittings and clamps, including cutting, making good the walls etc. and testing of joints complete: 50 mm dia. nominal bore	100.00	Meter
48	AS PER PWD ROAD SOR 01.01.2015 Human and other sculptures (a) 5 to 7 feet	2.00	Each
49	AS PER PWD ROAD SOR 01.01.2015 Human and other sculptures (b) 2 to 5 feet	2.00	Each
50	AS PER PWD ROAD SOR 01.01.2015 Cement art Mural work	15	Each
51	Electric SOR 01.07.2015 Supplying, installation, testing and commissioning of submersible pump set for water supply system with submersible motor directly coupled to multi-stage submersible pump of specified discharge capacity, head, delivery size in existing bore well including 2 sets of suitable size holding clamps made out of 50 mm X 6 mm MS flat, connection with suitable submersible cable of standard length etc. as required. 3.0 HP, three phase	1.00	Set

S.N.	PARTICULARS OF ITEMS	Quantity	UOM
52	Electric SOR 01.07.2015 Supply, installation, testing and commissioning of 5-7.5 HP 3 phase submersible motor starter cum control wall/ floor mounted type made out of not less than 1.6 mm thick MS sheet and comprising of following panel mounting switchgears there in including connection inter-connection etc. as required. a) Phase indicating lamps with fuses and toggle switches 1 set b) 5/7.5 HP 3 phase DOL starter with over load and no volt relay 1 No c) 32 A "C" curve TPMCB 1 No d) Voltmeter 0-500 V with selector switch 1 set e) Ammeter 0-10 A with CT's and selector switch 1 set.	1.00	Set
53	NON SOR ITEM Providing & Planting well developed & healthy (5' and above) orna mental plants with digging holes soil filling & chemical & biological treatment like ficus cycas chhatim, bottle palm, supari palm, musanda & avenue palm, tree including 6th month maintenance till well established as directed Engineer In charge	20	Each
54	NON SOR ITEM Providing & Planting well established flowering & orna mental plants or shrubs like nerium, bougainvillia, crotons, vidhya etc. with digging holes & chemical treatment including 6th month maintenance till well established as directed Engineer In charge	40	Each
55	NON SOR ITEM Providing & Planting well developed succulent healthy orna mental plants with digging chemical treatment like thuja, cycas, lolina etc, including 6th month maintenance till well established as directed Engineer In charge	25	Each
56	NON SOR ITEM Providing & fixing of Steel Bench Area 1.20x0.70 m Height 0.45 m above level seating ----- proper grip fixing with 1:2:4 Cement Concrete	9	Each
57	NON SOR ITEM Providing & fixing of Double Swing Jhula	3	Each

कार्यपालन अभियन्ता
नगर पालिक निगम, भिलाई

सहायक अभियन्ता
नगर पालिक निगम, भिलाई

उप अभियन्ता
नगर पालिक निगम, भिलाई