

# MUNICIPAL CORPORATION BHILAI (C.G.)

## NIT

कार्य का नाम :- वार्ड-69 एम.आई.जी.-1, 689 से 712 के समीप चैनलिंग फेंसिंग एवं पेवर ब्लॉक कार्य।


Pwd Building Sor 01.01.2015

| S.No. | Description and details of work   | Qty.    | Unit |
|-------|---|---------|------|
| 1     | Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.   | 15.50   | Cum  |
| 2     | Providing & laying 60mm thick precast interlocking concrete blocks of approved size (approx 305 sqcm) and shape/ pattern, over 40 mm thick average complete coarse sand bed with joints of 3mm thick filled by fine sand including leveling with surface vibrator, temping and sweeping etc. complete of minimum compressive strength of 250 kg/sq.cm Pigment Coloured (rubber mould) precast interlock concrete blocks | 155.00  | Sqm  |
| 3     | Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.<br>1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).  | 8.18    | Cum  |
| 4     | Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits. In all types of soil   | 10.65   | Cum  |
| 5     | Providing and laying nominal mix reinforcement cement concrete with crushed stone aggregate using concrete mixer in all works upto floor five level excluding cost of reinforcement and form work.<br>1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).  | 17.65   | Cum  |
| 6     | Providing and placing in position angle iron post and strut of required size including bottom to be split and bent at right angle in opposite direction for required length and drilling holes upto 10 mm dia as per requirement including priming coat with red oxide zinc chromate primer and placing the post/ strut in cement concrete block.   | 581.40  | Kg   |
| 7     | Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.<br>1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).  | 3.00    | Cum  |
| 8     | Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire all complete:Thermo-Mechanically treated bars   | 882.50  | Kg   |
| 9     | Steel work welded in built up sections/ framed work including cutting, hoisting, fixing in position and applying a priming coat of red oxide zinc chromate primer. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works.   | 1472.80 | Kg   |


| S.No. | Description and details of work   | Qty.   | Unit |
|-------|---|--------|------|
| 10    | Providing and fixing formwork including centering, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for:<br>Foundations, footings, base of columns and plinth beam in any shape and size.  | 100.00 | Sqm  |
| 11    | Providing and fixing in position chain linked steel wire fabric made of 4 mm dia G.I. wire of required width in mesh to concrete/ wooden/ angle iron posts including securing and screwing with 2mm dia G.I. wire, G.I. staples, G.I.U-nails or steel pins etc., complete. Aperture 50x50mm   | 210.00 | Sqm  |
| 12    | Painting exterior surface with PREMIUM ACRYLIC SMOOTH exterior paint of required shade as per manufacturer's specifications to give protective and decorative finish including cleaning washing of surface etc. complete with:<br>On new work (Two or more coats applied @ 1.43 ltr/ 10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/ 10 sqm) | 100.00 | Sqm  |



**Executive Engineer**  
**Municipal Corporation**  
**Bhilai (C.G)**



**Asstt. Engineer**  
**Municipal Corporation**  
**Bhilai (C.G)**



**Sub. Engineer**  
**Municipal Corporatio**  
**Bhilai (C.G)**