MUNICIPAL CORPORATION OF BHILAI

NIT वार्ड क्र. 29 कैलाश धाम शिव मंदिर में स्टील रेलिंग लगाने का कार्य।

(As Per PWD Building SOR 01.01.2015)

| | (As Per PWD Building SOR 01.01.2015) | | | |
|------|---|----------|-----|--|
| S.N. | PARTICULERS OF ITEMS | Quantity | UOM | |
| 1 1 | Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits. In all types of soils. | 6.84 | Cum | |
| 2 | Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:4:8 (1 cement: 4 coarse sand: 8 graded stone aggregate 40mm nominal size). | 1.74 | Cum | |
| 3 | Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size). | 3.600 | Cum | |
| 4 | Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire all complete:Thermo-Mechanically treated bars | 2.88 | Kg | |
| 5 | Providing and fixing form work including centring, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for: | | | |
| · A | Foundations, footings, bases of columns plinth beam, curtain wall in any shape and size and all type of wall below plinth level. | 24.00 | Sqm | |
| 6 | Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete. | 3.60 | Cum | |
| 7 | Brick work with modular fly-ash lime bricks (FaLG Bricks) confirming to IS:12894-2002 of class designation 4.0 in foundation and plinth in: Cement Mortar 1:6 (1 cement : 6 coarse sand) | 2.40 | Cum | |
| 8 | Providing and making 6mm thick cement plaster of mix: In Cement mortar 1:3 (1 cement : 3 fine sand) | 50.00 | Sqm | |
| 9 | Providing and making 12mm thick cement plaster of mix: In Cement mortar 1:4 (1 cement : 4 fine sand) | 90.00 | Sqm | |
| 10 | Providing and making 15mm thick cement plaster of mix: In Cement mortar 1:5 (1 cement : 5 fine sand) | 100.00 | Sqm | |
| .11 | Providing and fixing M.S. grill of approved pattern made of M.S. flats or square or round bars welded to steel frame of windows etc. including applying a priming coat welded to frame with all necessary fitting complete including applying a priming of red oxide zinc chromate primer. | 1350.00 | Kg | |
| 12 | Providing and fixing steel door/ window with M.S. sheet 1 mm thick, frame of angle iron, diagonal braces of angle/ flat iron of suitable size, 3.00 mm M.S. gusset plates at junctions and corners, all necessary fittings complete including applying a priming coat of red oxide zinc chromate primer. | 168.00 | Kg | |
| 13 | Providing stainless steel railing/ grill made of S.S. flats, hollow S.S. pipe or square/ rectangular sections of approved design fixing in stair case, balcony or other places with metal fasteners and stainless steel bolts etc complete. SS Grade 204 | 433.34 | Kg | |
| 14 | Providing and laying vitrified floor tiles with soluble salt printing, of size 600x600mm with water absorption less than 0.5% and conforming to IS: 15622 of approved make, laid on 20mm thick cement mortar 1:4 (1 cement: 4 coarse sand) including grouting the joints with white cement and matching pigments etc. complete. | 9.00 | Sqm | |

| | | Quantity | 1 |
|------|--|----------|-------------|
| S.N. | PARTICULERS OF ITEMS | | THE RESERVE |
| 15 | Painting exterior surface with ACRYLIC SMOOTH exterior paint of required shade as per manufacturer's specifications to give protective and decorative finish including cleaning washing of surface etc. complete with: | 100.00 | Sqm |
| | On new work (Two or more coats applied @ 1.43 ltr/ 10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/ 10 sqm) | | |
| 16 | Distempering with acrylic washable distemper to give an even shade. On new work (Two or more coats) | 140.00 | Sqm |
| 17 | Painting on new work (two or more coats) to give an even shade with: Premium Satin synthetic enamel paint | 8.40 | Sqm |
| 18 | Painting on new work (two or more coats) to give an even shade with: Premium Satin synthetic enamel paint | | |

Executive Engineer
Municipal Corporation
Bhilai

Assistant Engineer
Municipal Corporation
Bhilai

Sub Engineer

Municipal Corporation

Bhilai