## 6.

## MUNICIPAL CORPORATION OF BHILAI

## NIT वार्ड 30 नेपाली मोहल्ला में स्थित शिव मंदिर के समीप मंच का विस्तारीकरण कार्य।

(As Per PWD Building SOR 01.01.2015 & Electric SOR 01.06.2020)

| S.N.         | PARTICULERS OF ITEMS  | Quantity | UOM |
|--------------|---|----------|-----|
| 1            | Demolishing stone rubble masonry including arches, stacking of serviceable material and disposal of unserviceable material within 50 Metres lead. In cement mortar  | 2.40     | Cum |
| 2            | Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits. In all types of soils.   | 25.61    | Cum |
| 3            | Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.  1:4:8 (1 cement: 4 coarse sand: 8 graded stone aggregate 40mm nominal size).  | 3.03     | Cum |
| 4            | Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.  1:1½:3 (1 cement: 1½ coarse sand: 3 graded stone aggregate 20mm nominal size).   | 16.123   | Cum |
| 5            | Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire all complete:Thermo-Mechanically treated bars   | 1612.30  | Kg  |
|              | Providing and fixing form work including centring, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for:   | 21.66    | Sqm |
|              | Foundations, footings, bases of columns plinth beam, curtain wall in any shape and size and all type of wall below plinth level.  |          |     |
| (B)          | Columns, Pillars, Piers and likes- rectangular or square in shape   | 23.10    | Sqm |
| (C)          | Beams, lintels, cantilevers & walls   | 8.84     | Sqm |
| ( <u>D</u> ) | Suspended floors, roofs, access platform, balconies (plain surfaces) and shelves (cast in situ)   | 58.26    | Sqm |
| 7            | exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.   | 21.23    | Cum |
| -            | Brick work with modular fly-ash lime bricks (FaLG Bricks) confirming to IS:12894-2002 of class designation 4.0 in foundation and plinth in:  Cement Mortar 1:6 (1 cement : 6 coarse sand)   | 2.65     | Cum |
|              | Providing and laying damp proof course (upto 50mm thick) with plain cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded crushed stone aggregate 20mm nominal size) including form work   | 0.22     | Cum |
| 10           | Brick work with modular fly-ash lime bricks (FaLG Bricks) confirming to IS:12894-2002 of class designation 4.0 in foundation and plinth in: Cement Mortar 1:6 (1 cement: 6 coarse sand) Extra for brick work in superstructure above plinth level for every floor or part thereof in addition to rate for foundation and plinth:                          | 3.83     | Cum |
|              | Providing and making 6mm thick cement plaster of mix: In Cement mortar 1:3 (1 cement : 3 fine sand)   | 44.88    | Sqm |
|              | Providing and making 12mm thick cement plaster of mix: In Cement mortar 1:4 (1 cement : 4 fine sand)  | 19.14    | Sqm |
| 13           | Providing and making 15mm thick cement plaster of mix: In Cement mortar 1:5 (1 cement : 5 fine sand)  | 19.14    | Sqm |
| 14           | Cement concrete flooring with cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20mm) finished with a floating coat of neat cement.  50 mm thick   | 38.38    | Sqm |
| 15           | Providing and laying ceramic glazed floor tilesconforming to IS: 15622 of approved size, make, colour, shade laid on 20 mm thick Cement Mortar 1:4 (1 cement: 4 coarse sand) including pointing the joints with white cement mixed with matching pigment etc., complete. Size 300x300mm   | 43.29    | Sqm |
| 16           | Providing and fixing ceramic glazed wall tiles conforming to IS: 15622 of approved make, colours, shades and size on wall and dados over 12 mm thick bed of cement Mortar 1:3 (1 cement: 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm including pointing in white cement mixed with matching pigment complete. Size upto 200x300mm | 20.16    | Sqm |

| e N | PARTICULERS OF ITEMS  | Quantity | UUM |
|-----|---|----------|-----|
| 17  | Painting exterior surface with PREMIUM ACRYLIC SMOOTH exterior paint of required shade as per manufacturer's specifications to give protective and decorative finish including cleaning washing of surface etc. complete with:  On new work (Two or more coats applied @ 1.43 ltr/ 10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/ 10 sqm) | 19.14    | Sqm |
| 10  | Wall painting with acrylic luxury emulsion (plastic) paint of required shade to give an even shade.  On new work (two or more coats)  | 44.88    | Sqm |
| 19  | Add Extra For Electrification   | 11537.00 | LS  |

Executive Engineer
Municiapal Corporation
Bhilai

Assistant Engineer
Municipal Corporation
Bhilai

Sub Engineer
Municipal Corporation
Bhilai