

MUNICIPAL CORPORATION BHILAI

NIT

वार्ड क्र.31 शर्मा आश्रम के बाजू में स्थित शिव मंदिर के समीप भवन का विस्तारीकरण कार्य।

(AS PER PWD BUILDING SOR 01-01-2015 & ELECTRICAL SOR 01.06.2020)

SN	DETAILS OF ITEM	QTY.
1.	Demolishing brick masonry including arches, stacking of serviceable material disposal of unserviceable material within 50 metres lead In cement mortar @Rs 263 00/m ³	0.84 m ³
2.	Demolishing brick masonry including arches, stacking of serviceable material disposal of unserviceable material within 50 metres lead In cement mortar @Rs. 768 00/m ³	0.45 m ³
3.	Excavation for all types and size of foundation, trenches and drains or for any other purpose ---- lift and lead upto 50m including dressing and leveling of pits	36.22 m ³
4.	Providing and laying mechanically mixed cement concrete with crushed stone aggregate excluding cost of centering and shuttering 1 4 8	9.22 m ³
5.	Providing and filling in plinth with sand/Crusher dust and hard moorum under floor, including ---- cost of all labour, materials, T & P etc. complete required for the work.	10.00 m ³
6.	Providing and laying nominal mix reinforcement cement concrete with crushed stone aggregate using concrete mixer in all works upto floor five level excluding cost of reinforcement and form work. 1 1 ½ 3	25.67m ³
7.	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, ---- including cost of binding wire all complete. Thermo-Mechanically treated bars	2181.95 Kg
8.	Brick work with modular fly-ash lime bricks (FALG Bricks) confirming to IS:12894-2002 of class designation 40 in foundation and plinth in Cement Mortar 1 6	2.74 m ³
9.	Brick work with modular fly-ash lime bricks (FALG Bricks) confirming to IS:12894-2002 of class designation 40 Cement Mortar 1.6 Extra for brick work in superstructure. Above plinth and upto floor five level	15.33 m ³
10.	Providing and fixing formwork i/c centering, shuttering, strutting, staging, propping bracing etc. --, footings, base of columns and plinth beam in any shape and size	18.48 m ²
11.	Providing and fixing of formwork including centering, shuttering, strutting, staging, propping, bracings etc. --- plinth level. Columns- rectangular or square in shape	54.00 m ²
12.	Providing and fixing form work including centring, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for: Suspended floors, roofs, access platform, balconies (plain surfaces) and shelves (cast in situ)	60.64 m ²
13.	Steel work welded in built-up section trusses and framed work i/c cutting, hoisting, fixing in position and applying a priming coat of red lead paint.	333.96 Kg
14.	Providing and fixing steel door/ window with M.S. sheet 1mm thick, frame of angle iron, diagonal braces of angle/ flat iron of suitable size, 3.00 mm M.S. gusset plates at junctions and corners, all necessary fittings complete including applying a priming coat of red oxide zinc chromate primer.	246.00 Kg
15.	Providing & Laying damp proof course (up to 50mm thick) with plain cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded crushed stone aggregate 20mm nominal size) including formwork.	0.270 m ²
16.	6mm thick cement plaster a) In Cement mortar 1.3	60.64 m ²
17.	12mm thick cement plaster for cm 1.5 i/c neat cement punning.	91.36 m ²
18.	Providing and making 15mm thick cement plaster on the rough side of single or half brick wall of mix: In Cement Mortar 1 5 (1 cement : 5 fine sand)	90.36 m ²
19.	White washing with whiting to give an even shade. On new work (Three or more coats)	255.96 m ²
20.	Providing and laying vitrified floor tiles with soluble salt printing, of size 600x600mm with water absorption less than 0.5% and conforming to IS : 15622 of approved make, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand) including grouting the joints with white cement and matching pigments etc. complete.	51.95 m ²

21	Painting on new work (two or more coats) to give an even shade with: Satin synthetic enamel paint	2826 m ²
22	<u>Electrification work</u> As per electrical Sor 01.06.2020	23790.00 Lum-Sum


Executive Engineer
Municipal Corporation
Bhilai

Assistant Engineer
Municipal Corporation
Bhilai


Sub Engineer
Municipal Corporation
Bhilai