



# MUNICIPAL CORPORATION OF BHILAI

## NIT

कार्य का नाम :- सुपेला शा. अस्पताल में एल्युमिनियम पॉटिशन का संधारण कार्य।

S.N.	PARTICULERS OF ITEMS	Quantity	UOM
1	Providing and fixing double glazed hermetically sealed glazing in aluminium windows, ventilators and partition etc. with 6 mm thick clear float glass both side having 12 mm air gap including providing EPDM gasket, perforated aluminium spacers, desiccants, sealant (Both primary and secondary sealant) etc. complete.	70.00	SQM
2	Providing and fixing aluminium work for doors, windows, ventilators and partitions made out of extruded aluminium standard sections (main section with minimum 1.5mm thickness) conforming to IS: 733, IS: 1285 mitred and jointed mechanically including aluminium cleats, neoprene weather stripping gasket beveled edge beading, screws duly fixed in wall/ floor with fixing clips or hold fasteners or bolts and nuts as required aluminium sections shall be anodized transparent or dyed to approved shade according to IS: 1868, minimum anodic coating shall be of grade AC-15. (Glazing to be paid for separately: For fixed portion		
		200.00	KG
3	Providing and fixing 12mm thick pre-laminated particle board flat pressed with decorative lamination and balancing lamination on specified sides exterior Grade - I MDF Board 12 mm thick confirming to IS:14587, including fixed in aluminium doors, windows shutters and partition frames with C.P. brass/ stainless steel screws etc. complete. With decorative amination on one side and balancing lamination on other side.		
		140.00	SQM

  
सहायक अभियन्ता  
नगर पालिक निगम, भिलाई

  
उप अभियन्ता  
नगर पालिक निगम, भिलाई