

MUNICIPAL CORPORATION OF BHILAI

NIT

वार्ड क्र. 28 शंकर नगर में सांस्कृतिक भवन से खोरबाहरा पटेल के घर तक सीमेंटीकरण कार्य।

(As Per PWD BUILDING/ROAD SOR 01.01.2015)

SN	PARTICULERS OF ITEMS	QTY.	UNIT
1	Surface dressing of the ground including removing vegetation and making up undulations and inequalities not exceeding 15 cms in depth/ height including disposal of rubbish upto 1.5 m lift and lead upto 50m (at least 5m away from the dressed area).	2392.00	Sqm
2	Excavation in Soil (by Manual Means.) Excavation for roadway in soil using including loading in tipper for carrying of cut earth to embankment site and unloading with all lifts and lead upto 1000 meters as per relevant clauses of section 300.	73.60	Cum
3	Providing and laying cement concrete for plain concrete/ reinforced concrete i/c form work, shuttering complete in as per drawings and specifications.(For Village roads) P.C.C. M-25	138.00	Cum
4	Providing and laying cement concrete for plain concrete/ reinforced concrete i/c form work, shuttering complete in as per drawings and specifications.(For Village roads) P.C.C. M-30	294.40	Cum



Executive Engineer
Municipal Corporation
Bhilai



Assistant Engineer
Municipal Corporation
Bhilai



Sub Engineer
Municipal Corporation
Bhilai