

MUNICIPAL CORPORATION BHILAI

NIT

जोन क्र. 04 अंतर्गत हस्त पंपों के प्लेटफार्म का संधारण कार्य।

(As Per P.W.D. S.O.R. Building - 01.01.2015)

S. NO.	DETAILS OF ITEM	QTY.
1	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits. In all types of soils.	45.59 m ³
2	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).	52.089 m ³
3	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	25.123 m ³
4	Neat Cement Punning	428.74 m ²
5	Providing and fixing formwork i/c centering, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for a) Foundations, footings; base of columns and plinth beam in any shape and size	251.23 m ²


Executive Engineer
Municipal Corporation
Bhilai


Assistant Engineer
Municipal Corporation
Bhilai


Sub Engineer
Municipal Corporation
Bhilai