



MUNICIPAL CORPORATION BHILAI NIT


कार्य का नाम :- वार्ड क्रमांक 22 फलमंडी हनुमान मंदिर से श्रवण जायसवाल के घर तक सीमेंटीकरण कार्य।

(As Per PWD Building & Road SOR works w.e.f 01/01/2015 & NON Sor Item)

SN.	Details of Item	Qty.	Unit
1	Providing and laying cement concrete for plain concrete/ reinforced concrete i/c form work, shuttering complete in as per drawings and specifications.(For Village roads) P.C.C. M-10	7.25	m ³
2	Providing and laying cement concrete for plain concrete/ reinforced concrete i/c form work, shuttering complete in as per drawings and specifications.(For Village roads) P.C.C. M-30	52.50	m ³
3	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	30.00	m ³
4	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.	70.20	m ³
5	Non Sor Item <i>Fixed Rate</i> Cutting & Filling with bitumen in expansion joints of CC Road per CM depth & per CM width.	200.00	Rm


कार्यपालक अभियन्ता
नगर पालिक निगम, भिलाई


सहायक अभियन्ता
नगर पालिक निगम, भिलाई


उप अभियन्ता
नगर पालिक निगम, भिलाई