

# MUNICIPAL CORPORATION BHILAI (C.G.)


## NIT


कार्य का नाम :- जोन-01 अंतर्गत हुड़को विभिन्न स्थानों में पुलिया संधारण कार्य।

Pwd Building Sor 01.01.2015

S.No.	Description and details of work	Qty.	Unit
1	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits. In all types of soils.	15.36	Cum
2	Providing and laying nominal mix cement concrete with crushed stone aggregate using concrete mixer in foundation, plinth and at ground level excluding cost of form work. 1:4:8(1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size)	1.92	Cum
3	Providing and laying nominal mix reinforcement cement concrete with crushed stone aggregate using concrete mixer in foundation, plinth and at ground level excluding cost of form work.1:1.5:3	10.08	Cum
4	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding .....e as per drawings including cost of binding wire all complete. Thermo-Mechanically treated bars.	800.00	KG
5	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	5.76	Cum
6	Providing and fixing formwork i/c centering, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for : a)Foundations, footings; base of columns and plinth beam in any shape and size	42.56	Sqm

**Executive Engineer**  
Municipal Corporation  
Bhilai (C.G)

  
**Asstt. Engineer**  
Municipal Corporation  
Bhilai (C.G)

  
**Sub. Engineer**  
Municipal Corporatio  
Bhilai (C.G)