

MUNICIPAL CORPORATION BHILAI (C.G.)

(3)

Name of work :- <sup>nit</sup> वाड फे. 51 जेवळर - 04 रका रता मयदना मे यडक के  
 किलने पर कुडपारु मिमीतु काय।

As per Building SOR

S.No.	Description and details of work	Qty.	unit
1	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal	271.4	cum
2	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete	101.952	cum
3	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1:2:3	7.552	cum
4	Providing & laying 60mm thick precast interlocking concrete blocks of approved size (approx 305 sqcm) and shape/ pattern, over 40 mm thick average complete coarse sand bed with joints of 3mm thick filled by fine sand including leveling with surface vibrator, temping and sweeping etc. complete of minimum compressive strength of 250 kg/sq.cm pigment Coloured	1038.4	sqm
5	Carriage by mechanical transport upto 5 km lead: 1.26.1 Earth	217.12	cum

*[Handwritten mark]*

*[Signature]*  
**Asstt. Engineer**  
**Municipal Corporation**  
**Bhilai(C.G.)**

*[Signature]*  
**Sub Engineer**  
**Municipal Corporation**  
**Bhilai (C.G.)**