

MUNICIPAL CORPORATION BHILAI (C.G.)
nit

Name of work :- *लार्ड कृ. डर सेक्टर-04 सड़क - 27 स्टा डबल यूथम आर के मध्य कुटपटा निम्नीत काथी*

As per Building SOR

S.No.	Description and details of work	Qty.	unit
1	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal	136.784	cum
2	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete	65.072	cum
3	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. <i>PC 1:1 1/2:3</i>	4.2496	cum
4	Providing & laying 60mm thick precast interlocking concrete blocks of approved size (approx 305 sqcm) and shape/ pattern, over 40 mm thick average complete coarse sand bed with joints of 3mm thick filled by fine sand including leveling with surface vibrator, temping and sweeping etc. complete of minimum compressive strength of 250 kg/sq.cm <i>pigment coloured</i>	584.32	sqm
5	Carriage by mechanical transport upto 5 km lead: 1.26.1 Earth	122.176	cum

[Handwritten mark]

[Signature]
Asstt. Engineer
Municipal Corporation
Bhilai(C.G.)

[Signature]
Sub Engineer
Municipal Corporation
Bhilai (C.G.)