


## MUNICIPAL CORPORATION BHILAI (C.G.)

NIT

Name of work :- सड़क ईएमएस तथा एसएसएस स्कूल के सामने सड़क के दोनो किनारे पर फुटपाथ निर्माण कार्य

As per Building SOR 01.01.2015

S.No.	Description and details of work	Qty.	unit
1	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal	543	cum
2	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete	271	cum
3	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.	35.4	cum
4	Providing & laying 60mm thick precast interlocking concrete blocks of approved size (approx 305 sqcm) and shape/ pattern, over 40 mm thick average complete coarse sand bed with joints of 3mm thick filled by fine sand including leveling with surface vibrator, temping and sweeping etc. complete of minimum compressive strength of 250 kg/sq.cm	2360	sqm
5	Carriage by mechanical transport upto 5 km lead: 1.26.1 Earth	543	cum

  
EXECUTIVE ENGINEER  
MUNICIPAL CORPORATION  
BHILAI

  
ASSISTANT ENGINEER  
MUNICIPAL CORPORATION  
BHILAI

  
SUB ENGINEER  
MUNICIPAL CORPORATION  
BHILAI