


MUNICIPAL CORPORATION BHILAI (C.G.)

Name of work :- 915 54 વાડો ૫૩, ૨૮, ૨૯ ની વિશાલ ઓવરલેનિંગ નેટ લેવેલિંગ વેલોની ૫૨
 યુટીલિટી (બાઇલોડ વર્ક)

S.No.	Description and details of work	As per Building SOR	
		Qty.	unit
1	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal	768.891	cum
2	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete	283.68	cum
3	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. PCC 1:1 1/2:3.	18.912	cum
4a	Providing & laying 60mm thick precast interlocking concrete blocks of approved size (approx 305 sqcm) and shape/ pattern, over 40 mm thick average complete coarse sand bed with joints of 3mm thick filled by fine sand including leveling with surface vibrator, temping and sweeping etc. complete of minimum compressive strength of 250 kg/sq.cm Plain/ normal coloured precast interlock concrete block	1418.4	sqm
4b	Providing & laying 60mm thick precast interlocking concrete blocks of approved size (approx 305 sqcm) and shape/ pattern, over 40 mm thick average complete coarse sand bed with joints of 3mm thick filled by fine sand including leveling with surface vibrator, temping and sweeping etc. complete of minimum compressive strength of 250 kg/sq.cm. Pigment Coloured (rubber mould) precast interlock concrete blocks	1418.4	sqm
5	Carriage by mechanical transport upto 5 km lead: 1.26.1 Earth	543.72	cum



Asstt. Engineer
 Municipal Corporation
 Bhilai(C.G.)



Sub Engineer
 Municipal Corporation
 Bhilai (C.G.)