

**MUNICIPAL CORPORATION OF BHILAI**  
**NIT**

वार्ड क्र 38 दुर्गा माता मंदिर में ज्योति कक्ष निर्माण कार्य।

(As Per PWD Building SOR 01.01.2015 & Electric SOR 01.07.2015)

| SN  | PARTICULERS OF ITEMS   | QTY.    | UNIT |
|-----|--|---------|------|
| 1   | Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits. In all types of soils.                            | 14.42   | Cum  |
| 2   | Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.<br>1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).   | 3.66    | Cum  |
| 3   | Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.<br>1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).  | 12.21   | Cum  |
| 4   | Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire all complete:Thermo-Mechanically treated bars  | 1000.96 | Kg   |
| 5   | Providing and fixing form work including centring, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for:  |         |      |
| (A) | Foundations, footings, bases of columns plinth beam, curtain wall in any shape and size and all type of wall below plinth level.   | 17.00   | Sqm  |
| (B) | Columns, Pillars, Piers and likes- rectangular or square in shape  | 25.60   | Sqm  |
| (C) | Suspended floors, roofs, access platform, balconies (plain surfaces) and shelves (cast in situ)  | 27.04   | Sqm  |
| (D) | Beams, lintels, cantilevers & walls  | 17.40   | Sqm  |
| 6   | Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.  | 15.57   | Cum  |
| 7   | Brick work with modular fly-ash lime bricks (FaLG Bricks) confirming to IS:12894-2002 of class designation 4.0 in foundation and plinth in:<br>Cement Mortar 1:6<br>+ Extra for brick work in superstructure above plinth level for every floor or part thereof in addition to rate for foundation and plinth: | 8.59    | Cum  |
| 8   | Brick work with modular fly-ash lime bricks (FaLG Bricks) confirming to IS:12894-2002 of class designation 4.0 in foundation and plinth in:<br>Cement Mortar 1:6 (1 cement : 6 coarse sand)  | 0.84    | Cum  |
| 9   | Providing and making 6mm thick cement plaster of mix: In Cement mortar 1:3 (1 cement : 3 fine sand)  | 30.40   | Sqm  |
| 10  | Providing and making 12mm thick cement plaster of mix:<br>In Cement mortar 1:4 (1 cement : 4 fine sand)  | 55.20   | Sqm  |
| 11  | Providing and making 15mm thick cement plaster of mix:<br>In Cement mortar 1:5 (1 cement : 5 fine sand)  | 58.96   | Sqm  |
| 12  | Providing and fixing M.S. grill of approved pattern made of M.S. flats or square or round bars welded to steel frame of windows etc. including applying a priming coat welded to frame with all necessary fitting complete including applying a priming of red oxide zinc chromate primer.                     | 58.80   | Kg   |

| SN | PARTICULARS OF ITEMS   | QTY.    | UNIT |
|----|--|---------|------|
| 13 | Providing and fixing steel door/ window with M.S. sheet 1mm thick, frame of angle iron, diagonal braces of angle/ flat iron of suitable size, 3.00 mm M.S. gusset plates at junctions and corners, all necessary fittings complete including applying a priming coat of red oxide zinc chromate primer.  | 135.00  | Kg   |
| 14 | Providing and laying ceramic glazed floor tiles conforming to IS : 15622 of approved size, make, colour, shade laid on 20 mm thick Cement Mortar 1:4 (1 cement : 4 coarse sand) including pointing the joints with white cement mixed with matching pigment etc., complete.  | 21.16   | Sqm  |
| 15 | Providing and fixing ceramic glazed wall tiles conforming to IS : 15622 of approved make, colours, shades and size on wall and dados over 12 mm thick bed of cement Mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm including pointing in white cement mixed with matching pigment complete.  | 15.00   | Sqm  |
| 16 | Providing & laying 60mm thick precast interlocking concrete blocks of approved size (approx 305 sqcm) and shape/ pattern, over 40 mm thick average complete coarse sand bed with joints of 3mm thick filled by fine sand including leveling with surface vibrator, temping and sweeping etc. complete of minimum compressive strength of 250 kg/sq.cm<br>Plain/ normal coloured precast interlock concrete block | 16.00   | Sqm  |
| 17 | Painting exterior surface with PREMIUM ACRYLIC SMOOTH exterior paint of required shade as per manufacturer's specifications to give protective and decorative finish including cleaning washing of surface etc. complete with:<br>On new work (Two or more coats applied @ 1.43 ltr/ 10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/ 10 sqm)  | 58.96   | Sqm  |
| 18 | Distemping with acrylic washable distemper to give an even shade.<br>On new work (Two or more coats)   | 85.60   | Sqm  |
| 19 | Painting on new work (two or more coats) to give an even shade with:<br>Satin synthetic enamel paint   | 2.94    | Sqm  |
| 20 | Add For Electrification, Sanitary & Water Supply   | 7281.00 | LS   |

  
Executive Engineer  
Municipal Corporation  
Bhilai

Assistant Engineer  
Municipal Corporation  
Bhilai

  
Sub Engineer  
Municipal Corporation  
Bhilai