

MUNICIPAL CORPORATION, BHILAI ZONE 05 DIST-DURG

NIT


AS PER P.W.D building SOR W.E.F 01.01.2015.

PLACE OF WORK- PAVER BLOCK at SECTOR 06 IN FRONT OF STREET 50 WARD NO 56.

S.NO.	ITEM	QTY	UNIT
1	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits. AS PER ITEM No. 1.1.1 In all types of soil	24.32	Cum
2	Providing & laying 60mm thick precast interlocking concrete blocks of approved size (approx 305 sqcm) and shape/ pattern, over 40 mm thick average complete coarse sand bed with joints of 3mm thick filled by fine sand including leveling with surface vibrator, temping and sweeping etc. complete of minimum compressive strength of 250 kg/sq.cm	243.2	SQM


EXECUTIVE ENGINEER
MUNICIPAL CORPORATION,
BHILAI


ASSISTENT ENGINEER
MUNICIPAL CORPORATION,
BHILAI


SUB ENGINEER
MUNICIPAL CORPORATION,
BHILAI