




**MUNICIPAL CORPORATION BHILAI (C.G.)**  
**NIT**

Line of work :- वार्ड क्र. 57 सेक्टर 06 सडक 33-34 के मध्य मंच का संधारण कार्य।

| S.No. | Description and details of work   | Qty.  | unit |
|-------|---|-------|------|
| 1     | 15 mm thick Table rubbed polished Granite stone slab flooring laid over 20mm (Average) thick base of cement mortar 1:4 (1 cement : 4 coarse sand) laid and jointed with grey cement slurry including rubbing and polishing etc. complete. (Area of slab should be 0.50 sqm and above) | 140   | sqm  |
| 2     | Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1½:3 (1 cem   | 11.25 | cum  |

  
EXECUTIVE ENGINEER  
MUNICIPAL CORPORATION  
BHILAI

  
ASSISTANT ENGINEER  
MUNICIPAL CORPORATION  
BHILAI

  
SUB ENGINEER  
MUNICIPAL CORPORATION  
BHILAI