MUNICIPAL CORPORATION OF BHILAI

DETAILED ESTIMATE

वार्ड क्र. 28 मंच के चारों तरफ स्टील रेलिंग जाली लगाने का कार्य।

(As Per PWD Building SOR 01.01.2015) **UOM** Quantity S.N. PARTICULERS OF ITEMS Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including Cum disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), 6.84 1 including dressing and leveling of pits. In all types of soils. Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete Cum 1.74 2 mixer in all works upto plinth level excluding cost of form work. 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size). Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using Cum 3.600 3 concrete mixer in all works upto plinth level excluding cost of form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size). Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, Kg bending, binding etc. complete as per drawings including cost of binding wire all complete: Thermo-288.00 4 Mechanically treated bars Providing and fixing form work including centring, shuttering, strutting, staging, propping bracing etc. 5 complete and including its removal at all levels, for: Foundations, footings, bases of columns plinth beam, curtain wall in any shape and size and all type of 24.00 Sqm (A) wall below plinth level. Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not Cum 3.60 exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including 6 dressing etc. complete. Brick work with modular fly-ash lime bricks (FaLG Bricks) confirming to IS:12894-2002 of class Cum 2.40 7 designation 4.0 in foundation and plinth in: Cement Mortar 1:6 (1 cement : 6 coarse sand) Providing and making 6mm thick cement plaster of mix: In Cement mortar 1:3 (1 cement: 3 fine sand) 50.00 Sqm 8 Providing and making 12mm thick cement plaster of mix: 9 90.00 Sqm In Cement mortar 1:4 (1 cement : 4 fine sand) Providing and making 15mm thick cement plaster of mix: 10 100.00 Sqm In Cement mortar 1:5 (1 cement: 5 fine sand) Providing and fixing M.S. grill of approved pattern made of M.S. flats or square or round bars welded to 11 steel frame of windows etc. including applying a priming coat welded to frame with all necessary fitting 1350.00 Kg complete including applying a priming of red oxide zinc chromate primer. Providing and fixing steel door/ window with M.S. sheet 1mm thick, frame of angle iron, diagonal braces of angle/ flat iron of suitable size, 3.00 mm M.S. gusset plates at junctions and corners, all necessary 168.00 Kg fittings complete including applying a priming coat of red oxide zinc chromate primer. Providing stainless steel railing/grill made of S.S. flats, hollow S.S. pipe or square/rectangular sections of approved design fixing in stair case, 13 balcony or other places with metal fasteners and stainless steel bolts etc complete. 217.90 Kg SS Grade 204 Providing and laying vitrified floor tiles with soluble salt printing, of size 600x600mm with water absorption less than 0.5% and conforming to IS: 15622 of approved make, laid on 20mm thick cement 14 mortar 1:4 (1 cement: 4 coarse sand) including grouting the joints with white cement and matching 9.00 Sqm pigments etc. complete.

s	.N.	PARTICULERS OF ITEMS	Quantity	UOM
	15	Painting exterior surface with ACRYLIC SMOOTH exterior paint of required shade as per manufacturer's specifications to give protective and decorative finish including cleaning washing of surface etc. complete with: On new work (Two or more coats applied @ 1.43 ltr/ 10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/ 10 sqm)	100.00	Sqm
	16	Distempering with acrylic washable distemper to give an even shade. On new work (Two or more coats)	140.00	Sqm
	17	Painting on new work (two or more coats) to give an even shade with: Premium Satin synthetic enamel paint	8.40	Sqm

Executive Engineer
Municiapal Corporation
Bhilai

Assistant Engineer Municipal Corporation Bhilai Sub Engineer

Municipal Corporation

Bhilai