(D)

NAGAR NIGAM BHILAI

N.I.T.

वार्ड क्र.—14 बाबादीप सिंह नगर स्थित सार्वजनिक गार्डन में पाथवे निर्माण कार्य।

AS PER BUILDING SOR 01.01.2015 OTY UNIT			
S.N	PARTICULAR	VII	UNII
1	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits.		
	In all types of soil	41.86	cum
2	Providing & laying 60mm thick precast interlocking concrete blocks of approved size (approx 305 sqcm) and shape/ pattern, over 40 mm thick including leveling with surface vibrator, temping and sweeping etc. complete of minimum compressive strength of 250 kg/sq.cm		
	Plain/ normal coloured precast interlock concrete block		
		418.60	sqm
3	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.		
	1:11/2:3 (1 cement : 11/2 coarse sand : 3 graded stone aggregate 20mm nominal size).		
		2.47	cum

DY.

ASSTT.ENGINEER

Nagar Palik Nigam, Bhilai

SUB ENGINEER

Nagar Palik Nigam, Bhilai