

# MUNICIPAL CORPORATION OF BHILAI

## NIT

कार्य का नाम:- वार्ड क्रमांक 47 सेक्टर 01 गार्डन पूर्व का संधारण कार्य।

As Per PWD Building SOR 01.01.2015 NON SOR ITEM,

S.N.	PARTICULARS OF ITEMS	Quantity	UOM
1	Distemping with acrylic washable distemper to give an even shade.On old work (one or more coats)	400.00	Sqm
2	Providing & laying 60mm thick precast interlocking concrete blocks of approved size (approx 305 sqcm) and shape/ pattern, over 40 mm thick average complete coarse sand bed with joints of 3mm thick filled by fine sand including leveling with surface vibrator, temping andsweeping etc. complete of minimum compressive strength of 250 kg/sq.cm Pigment Coloured (rubber mould) precast interlock concrete blocks	25.00	Sqm
3	Grassing with 'Doob' grass including watering and maintenance of the lawn for 30 days or more till the grass forms a thick lawn free from weeds and fit for mowing including supplying good earth if needed (the good earth shall be paid for separately).In rows 5 cm apart in either direction.	300.00	Sqm
4	NON SOR ITEM Maintanance of Garden including plant cutting, cleaning, watering on plants and providing Gaurd( 24 hrs or 3 shift)	612.00	Day

कार्यपालक अभियन्ता  
नगर पालिक निगम, भिलाई

सहायक अभियन्ता  
नगर पालिक निगम, भिलाई

उप अभियन्ता  
नगर पालिक निगम, भिलाई