MUNICIPAL CORPORATION, BHILAI

(As per Building SOR wef- 01.01.2015)

Name Of Work वार्ड कं. 64 सें. 10 बी मार्केट के सामने नाली निर्माण कार्य।

0. 🚜	Details Of Item	Qty,	Unit
1	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff up to 1.5 m lift and lead up to 50m (at least 5m away from the excavated area), including dressing and leveling of pits. In all type of soil.	79.2	cum
2	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works up to plinth level excluding cost of form work. 1:3:6 graded stone aggregate 40mm nominal size.	13.2	cum
3	Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:11/2:3 graded stone aggregate 20mm nominal size).	27.6	eum
4	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire in foundation and plinth all complete: Thermo-Mechanically treated bars, FE 415.	1822	kg
5	Providing and fixing form work including centering, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for: Foundations, footings, base of columns and plinth beam levels, for: Foundations, footings, base of wall below plinth level.	192	sqm
6	Carriage by mechanical transport for sign to	63.36	cum
7	Filling from available excavated stuff (Excluding rock) in trenches, plinth, sides of foundation etc. in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering with a lead upto 50 M. and lift upto 1.5 M.	9.6	cum

sub Engineer Nagar Palik Nigam Bhilai

Assi.Engineer Nagar Palik Nigam Bhilai

Ju Engineer Nggin Ralik Nigam Bhilat र-६ जुनर पालिक जिनम

भिलाई