

MUNICIPAL CORPORATION OF BHILAI

कार्य का नाम :- वार्ड क्र 47 सेक्टर NIT 01 विवेकानंद गार्डन भाग-2 में संधारण कार्य ।

(As Per PWD Building SOR 01.01.2015)

S.N.	PARTICULARS OF ITEMS	Quantity	UOM
1	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits. In all types of soil	33.31	Cum
2	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).	16.65	Cum
3	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	24.98	Cum
4	Providing and laying ceramic glazed floor tiles conforming to IS : 15622 of approved size, make, colour, shade laid on 20 mm thick Cement Mortar 1:4 (1 cement : 4 coarse sand) including pointing the joints with white cement mixed with matching pigment etc., complete.	168.35	Sqm
5	Grassing with 'Doob' grass including watering and maintenance of the lawn for 30 days or more till the grass forms a thick lawn free from weeds and fit for mowing including supplying good earth if needed (the good earth shall be paid for separately). In rows 5 cm apart in either direction.	500.00	Sqm
6	Providing and planting following herbs in garden including preparation of soil, base plantation, providing and spreading different fertilizers, soil and sand: Hedges like Alife, Dorenta, Tikoma etc	100.00	Each
7	Furn like Arica, China etc (3 year old)	70.00	Each
8	Hibiscus (Flower)/ Rose	70.00	Each
9	Carpet grass (well developed)	60.00	Each

कार्यपालन अभियन्ता
नगर पालिक निगम, भिलाई

सहायक अभियन्ता
नगर पालिक निगम, भिलाई

उप अभियन्ता
नगर पालिक निगम, भिलाई