


# MUNICIPAL CORPORATION BHILAI (C.G.)

## NIT


Name of work :- जोन क्र. 05 वार्ड 66 सेक्टर 07 के विभिन्न सड़कों में स्थित उद्यानों का संधारण कार्य।

As per Building SOR 01.01.2015% electrical SOR 2020

S.No.	Description and details of work	Qty.	Unit
1	Supplying and stacking of good earth at site including royalty, loading, unloading and carriage upto 5 km (earth measured in stacks will be reduced by 20% for payment).	1257.8	cum
2	Spreading of sludge, dump manure or/and good earth in required thickness (Cost of sludge, dump manure or/and good earth to be paid separately).	1257.8	cum
3	Supplying, installation, testing and commissioning of submersible pump set for water supply system with submersible motor directly coupled to multi-stage submersible pump of specified discharge capacity, head, delivery size in existing bore well including 2 sets of suitable size holding clamps made out of 50 mm X 6 mm MS flat, connection with suitable submersible cable of standard length etc. as per specification and IS: 694 (2010). Note: submersible Cable should be rust proof, safe from oil / Grease and under water Chemical / abrasion Resistant. 1.0 HP, single phase	1	each

  
EXECUTIVE ENGINEER  
MUNICIPAL CORPORATION  
BHILAI

  
ASSISTANT ENGINEER  
MUNICIPAL CORPORATION  
BHILAI

  
SUBENGINEER  
MUNICIPAL CORPORATION  
BHILAI