

MUNICIPAL CORPORATION BHILAI (C.G.)


NIT

NAME OF WORK - वाई-SS सेक्टर - G MSCL कारोनी आंगणवाडी में प्रकाश व्यवस्था एवं अन्य संभारण कार्य ।


As per C.G PWD Building sor w.e.f- 01-01-2015 and elec sor 2020

Sno	Particulars	Qty	Unit
1	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits. In all types of soil	15.00	Cum
2	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.	7.50	Cum
3	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).	7.50	Cum
4	Providing and fixing form work including centring, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for: Foundations, footings, bases of columns plinth beam, curtain wall in any shape and size and all type of wall below plinth level.	3.00	Sqm
5	Providing & laying 60mm thick precast interlocking concrete blocks of approved size (approx 305 sqcm) and shape/ pattern, over 40 mm thick average complete coarse sand bed with joints of 3mm thick filled by fine sand including leveling with surface vibrator, temping and sweeping etc. complete of minimum compressive strength of 250 kg/sq.cm Pigment Coloured (rubber mould) precast interlock concrete blocks	7.50	SQM
6	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	0.60	Cum
7	Wiring for light/ fan/ exhaust fan / call bell point with 3x1.5 sqmm FRLS PVC insulated stranded copper conductor wire for phase, neutral and earth in concealed FRLS PVC conduit (heavy duty, thickness of pipe should be 2 mm) with 5/6 amp piano type switch, phenolic laminated sheet, suitable size M.S. box etc as per specification and IS: 694 (2010), IS: 9537 (2000 Part 5)		
	Short Point	2.00	Point
	Medium Point	2.00	Point
	Long Point	2.00	Point

8	Supplying, installation, testing and commissioning of following sizes ceiling fan including wiring the down rods of standard length up to 30 cm with 1.5 sq. mm FRLS PVC insulated, copper conductor, single core cable, earthing etc. complete as required. P.F. should be greater than 0.9, with BEE Star rating from 3 star and above, IS: 374:2019 including all amendments. 1200 mm sweep	2.00	Each
9	Supplying, installation, testing and commissioning of following sizes Pedestal fan with telescopic arrangement for height adjustment and standard wiring/connection etc complete as per specification. P.F. should be greater than 0.9 400 mm sweep	2.00	Each
10	Supplying, installation, testing and commissioning of following LED tube light fitting including batten with Electronic Driver Heat sink Capacitor complete with all other accessories on surface/ in false ceiling, including connection, earthing etc complete as per specification and IP20, P.F. should be greater than 0.9. LED chip efficacy ratio \geq 100 lumens /watt. 10 watt {2 feet}	4.00	Each
11	Supplying and laying following sizes one number FRLS PVC insulated/XLPE, PVC sheathed, steel armoured, aluminium conductor power cable of 1.1 KV grade direct in ground at a depth not less than 40 cm and upto 90 cm including excavation, sand cushioning, protective covering and refilling the trench etc as per specification, IS: 1554 (1988, Part 1) / IS: 7098 (1988, Part 1). 4 x 10 sq. mm.	105.00	Metre
12	Supplying, installation, testing and commissioning of submersible pump set for water supply system with submersible motor directly coupled to multi-stage submersible pump of specified discharge capacity, head, delivery size in existing bore well including 2 sets of suitable size holding clamps made out of 50 mm X 6 mm MS flat, connection with suitable submersible cable of standard length etc. as per specification and IS: 694 (2010). Note: submersible Cable should be rust proof, safe from oil / Grease and under water Chemical / abrasion Resistant. 1.0 HP, single phase	1.00	Each
13	Supplying and fixing of following sizes 'B' class G I pipe with welded steel flange of suitable size at both the end of every pipe length, fixing with submersible pump and lowering with the pump in the bore well including necessary rubber gasket, nuts & bolts etc. as per specification. 40 mm dia.	45.00	Metre


EXECUTIVE ENGINEER
MUNICIPAL CORPORATION
BHILAI


ASSISTANT ENGINEER
MUNICIPAL CORPORATION
BHILAI


SUBENGINEER
MUNICIPAL CORPORATION
BHILAI