

# MUNICIPAL CORPORATION- BHILAI

work :-

MIT  
 वार्ड क. 57 सेक्टर - 06 पुलिस कन्ट्रोल रूम को 12-21 नं. इलाका  
 सवारी-रथ  
 BUILDING SOR-2015 & NON SOR

no	Particulars	Qty
1	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits.	
	In all types of soil	8
2	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.	8
3	Path way Providing & laying 60mm thick precast interlocking concrete blocks of approved size (approx 305 sqcm) and shape/ pattern, over 40 mm thick average complete coarse sand bed with joints of 3mm thick filled by fine sand including leveling with surface vibrator, tamping and sweeping etc. complete of minimum compressive strength of 250 kg/sq.cm	
	Pigment Coloured (rubber mould) precast interlock concrete blocks	80
4	Path way Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	1.6
5	Carriage by mechanical transport upto 5 km lead: 1.26.1 Earth	8

## TOTAL

Providing and applying 2 coats wall care putty (Cementitious putty) to internal walls (Concrete walls), ceilings. Cost to include al lead, lift, base preparation of surfaces to line & level, rubbing the the surface. All wall undulations shall be covered up using putty and the walls shall be brought to proper line and level as per the directions or instructions of the project manager.

Providing & applying two coats of painting with Oil Bound Distemper of approved brand, shade & manufacture over a coat of primer including preparing the surface to line & level & to receive the paintings for ceilings at all levels with primer etc., complete as specified including all other necessary related work, leads & lifts etc., complete as specified in the drawings, specifications and as directed by Project Manager.

Preparing the surfaces to line & level, removing the dust, dirt, repairing dents, providing and applying white cement paint with 1 coat primer & 2 or more finishing coats of based cement paint mixed with clean water of required proportions as per manufacturers specification including curing, scaffolding etc., complete as specified including all other necessary related work, leads & lifts etc., as specified in the drawings, specifications and as directed by Project Manager.

210

Providing & applying two coats of painting with Acrylic Emulsion paint of approved brand, shade & manufacture over a coat of primer including preparing the surface to line & level & to receive the paintings for internal walls (Concrete walls) at all levels with primer etc., complete as specified including all other necessary related work, leads & lifts etc., complete as specified in the drawings, specifications and as directed by Project Manager.

Providing two coats of painting with exterior grade weathershield Emulsion paint of approved brand, shade & manufacture over a coat of primer including preparing the surface to receive the paintings for External walls at all levels with primer etc., complete as specified including all other necessary related work, leads & lifts etc., as specified in the drawings, specifications and as directed by Project Manager. Rate is inclusive of surface preparation to line & level with all necessary tools & tackles, etc. maintaining proper line, level and grooves, as specified

B

Total

*Handwritten signature*

*Handwritten signature*  
110

उप अभियंता  
आयुर्विभाग क्रमांक 5 सेक्टर-6  
जयपुर पालिक निगम  
भिलाई