

MUNICIPAL CORPORATION OF BHILAI

NIT

कार्य का नाम :- वार्ड 65 सेक्टर 7 तालाब के आस पास संधारण कार्य।

S.N.	PARTICULERS OF ITEMS	Qty.	Rate
1	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits.(In all types of soils.)	185.00	cum
2	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.	371.00	Cum
3	Providing & laying 60mm thick precast interlocking concrete blocks of approved size (approx 305 sqcm) and shape/ pattern, over 40 mm thick average complete coarse sand bed with joints of 3mm thick filled by fine sand including leveling with surface vibrator, temping and sweeping etc. complete of minimum compressive strength of 250 kg/sq.cm Pigment Coloured (rubber mould) precast interlock concrete blocks	632.00	SQM
4	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	4073.00	Cum
5	Carriage by mechanical transport upto 5 km lead:	111.00	Cum
6	15mm thick cement plaster on the rough side of single or half brick wall of mix: In Cement Mortar 1:6 (1 cement : 6 fine sand)	107.00	SQM
7	Wall painting with acrylic luxury emulsion (plastic) paint of required shade to give an even shade. On new work (two or more coats)	52.50	SQM
8	Painting on old work (one or more coats) to give an even shade with: 14.23.1 Satin synthetic enamel paint	35.00	SQM
9	15 mm thick Table rubbed polished Granite stone slab flooring laid over 20mm (Average) thick base of cement mortar 1:4 (1 cement : 4 coarse sand) laid and jointed with grey cement slurry including rubbing and polishing etc. complete. (Area of slab should be 0.50 sqm and above)	1796.00	SQM

EXECUTIVE ENGINEER
MUNICIPAL CORPORATION
BHILAI

ASSISTANT ENGINEER
MUNICIPAL CORPORATION
BHILAI

Sub Engineer
Municipal Corporation
Bhilai (C.G.)