NAGAR PALIK NIGAM BHILAI				
1	NIT			
	वार्ड क्र.—16 प्रगति नगर में सी.सी. रोड निर्माण कार्य।			
	AS PER ROAD/BUILDING SOR (01.01.2015)			
S.N.	PARTICULAR	Q	U	
1	Excavation in Soil (by Mechanical Means.) Excavation for roadway in soil using mechanical means including loading in tipper for carrying of cut earth to embankment site and unloading with all lifts and lead upto 1000 meters as per relevant clauses of section			
	300.	180.00	cun	
2	Providing and filling in plinth with sand/ Crusher dust and hard moorumunder floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.			
		60.00	cum	
3	Providing and laying cement concrete for plain concrete/ reinforced concrete i/c form work, shuttering complete in as per drawings and specifications.(For Village roads			
	P.C.C. M-10	90.00	cum	
	P.C.C. M-30	90.00	cum	
4	Carriage by mechanical transport upto 5 km lead:			
	Earth	540.00	cum	

ASSISTANT ENGINEER

NAGAR PALIK NIGAM, BHILAI

SUB ENGINEER NAGAR PALIK (IGAM, BHILAI