

NAGAR PALIK NIGAM BHILAI**NIT**

वार्ड क्र.-13 राजीव नगर में कारु के घर के पीछे एवं मालू बाई के घर के पास नाली संधारण कार्य।

(AS PER P.W.D BUILDING S.O.R. W.E.F. 01.01.2015)

S.NO	PARTICULAR	Q	U
1	Excavation for all types and sizes of foundations, trenches and drains or ... m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits.		
	In all types of soil	75.60	cum
3	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.		
	1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).	12.60	cum
4	Providing and fixing form work including centring, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for:		
	Foundations, footings, base of columns and plinth beam in any shape and size.	280.00	sqm
5	Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.		
	1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	31.50	cum
6	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire in foundation and plinth all complete:		
	Thermo-Mechanically treated bars FE 415	1260.00	kg
7	Filling from available excavated stuff (Excluding rock) in trenches, plinth, sides of foundation etc. in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering with a lead upto 50 M. and lift upto 1.5 M.	14.00	cum
8	Carriage by mechanical transport for 5 km lead:		
	Earth	75.60	cum

ASSTT.ENGINEER

Nagar Palik Nigam, Bhilai


SUB ENGINEER

Nagar Palik Nigam, Bhilai