

MUNICIPAL CORPORATION BHILAI (C.G.)

nit

Name of work :- *वॉल-57 क्रमांक-6 कालीबाडी के लगी पतल कलाक अंश 1*

As per C.G PWD Building sor w.e.f- 01-01-2015

Sno	Particulars	Qty	Unit
1	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits.		
	In all types of soil	129.60	
	Wall	129.60	Cum
2	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc.	86.40	
	Path way	86.40	Cum
3	Providing & laying 60mm thick precast interlocking concrete blocks of approved size (approx 305 sqcm) and shape/ pattern, over 40 mm thick average complete coarse sand bed with joints of 3mm thick filled by fine sand including leveling with surface vibrator, temping and sweeping etc. complete of minimum compressive strength of 250 kg/sq.cm		
	Pigment Coloured (rubber mould) precast interlock concrete blocks	324.00	
	Path way	324.00	SQM
4	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	4.32	Cum
5	Carriage by mechanical transport upto 5 km lead: 1.26.1 Earth	129.60	Cum

*[Signature]*  
Sub Engineer  
Municipal Corporation  
Bhilai (C.G.)

*[Signature]*  
कार्यपालन अभियंता  
अनुविभाग क्रमांक 6 सेक्टर-8  
नगर पंचायत निगम  
भिलाई  
प्राक्कलन पंजी क्र.....

*[Signature]*  
सहायक अभियंता  
अनुविभाग क्रमांक 6 सेक्टर-8  
नगर पंचायत निगम  
भिलाई  
दिनांक.....