

MUNICIPAL CORPORATION BHILAI (C.G.)


NIT


Name of work :- वाई.क. 66 सेक्टर-07 अडक-25 से अडक-33 फीस
 भाडा का अकारण करी

As per Building SOR 01.01.2015

S.No.	Description and details of work	Qty.	unit
1	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal	67.8	cum
2	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.1.1.5.3	9.492	cum
3	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.	33.9	cum
4	Providing & laying 60mm thick precast interlocking concrete blocks of approved size (approx 305 sqcm) and shape/ pattern, over 40 mm thick average complete coarse sand bed with joints of 3mm thick filled by fine sand including leveling with surface vibrator, temping and sweeping etc. complete of minimum compressive strength of 250 kg/sq.cm rubble mould	284.76	sqm
5	Carriage by mechanical transport upto 5 km lead: 1.26.1 Earth	54.24	cum

**EXECUTIVE ENGINEER
 MUNICIPAL CORPORATION
 BHILAI**


**ASSISTANT ENGINEER
 MUNICIPAL CORPORATION
 BHILAI**


**Sub Engineer
 Municipal Corporation
 Bhilai (C.G.)**