

MUNICIPAL CORPORATION OF BHILAI

NIT

वार्ड क्र. 49 सेक्टर 02 सड़क 04 में मिनी उद्यान निर्माण कार्य।

As Per PWD Building/Road SOR 01.01.2015, Electrical SOR 01.06.2020 & NON SOR ITEM

N.	PARTICULARS OF ITEMS	Quantity	UOM	Rate
1	Surface dressing of the ground including removing vegetation and making up undulations and in-equalities not exceeding 15 cms in depth/ height including disposal of rubbish upto 1.5 m lift and lead upto 50m (at least 5m away from the dressed area).	200	sqm	7.20
2	Providing and planting following herbs in garden including preparation of soil, base plantation, providing and spreading different fertilizers, soil and sand: Hedges like Alife, Dorenta, Tikoma etc	1000	Each	14.00
3	Spreading of sludge, dump manure or/and good earth in required thickness (Cost of sludge, dump manure or/ and good earth to be paid separately).	80	Cum	17.50
4	Hibiscus (Flower)/ Rose	100	Each	26.50
5	Furn like Arica, China etc (3 year old)	50	Each	125.00
6	Supplying and stacking of good earth at site including royalty, loading, unloading and carriage upto 5 km (earth measured in stacks will be reduced by 20% for payment).	12	Cum	201.00
7	Supplying and stacking at site well decayed cow dung manure from approved source, including loading, unloading and carriage upto 5 km (manure measured in stacks will be reduced by 8% for payment).	10	Cum	236.00
8	Carpet grass (well developed)	100.00	sqm	263.00
9	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire all complete: Thermo-Mechanically treated bars	296.8	Kg	54.50
10	Painting on new work (two or more coats) to give an even shade with: Satin synthetic enamel paint	5.20	sqm	55.00
11	Painting on new work (two or more coats) to give an even shade with: Satin synthetic enamel paint	5.10	sqm	55.00
12	Painting on new work (two or more coats) to give an even shade with: Aluminium paint	195.00	sqm	58.50
13	Steel work welded in built up sections/ framed work including cutting, hoisting, fixing in position and applying a priming coat of red oxide zinc chromate primer. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works.	506.57	Kg	68.00

S.N.	PARTICULARS OF ITEMS	Quantity	UOM	Rs
14	Providing and placing in position angle iron post and strut of required size including bottom to be split and bent at right angle in opposite direction for required length and drilling holes upto 10 mm dia as per requirement including priming coat with red oxide zinc chromate primer and placing the post/ strut in cement concrete block.	151.164	Kg	69.50
15	Painting exterior surface with PREMIUM ACRYLIC SMOOTH exterior paint of required shade as per manufacturer's specifications to give protective and decorative finish including cleaning washing of surface etc. complete with: On new work (Two or more coats applied @ 1.43 ltr/ 10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/ 10 sqm)	122.52	sqm	74.50
16	Providing and making 12mm thick cement plaster of mix: In Cement Mortar 1:4 (1 cement : 4 fine sand)	5.52	sqm	103.00
17	Providing and fixing formwork including centering, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for:(A) Foundations, footings, base of columns and plinth beam in any shape and size.	30.00	sqm	139.00
18	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits.In all types of soil	61.045	Cum	185.00
19	Boring/drilling bore well perfectly vertical for the specified depth suitable to receive required dia for casing/ strainer pipe, by suitable method prescribed in IS: 2800 (part I), including collecting samples from different strata, preparing and submitting strata chart/bore log, including hire & running charges of all equipments, tools, plants & machineries required for the job, all complete as per direction of Engineer-in-charge upto 90 metre depth below ground level. All types of soil. 125 mm dia.	30	Meter	321.00
20	Providing and fixing in position chain linked steel wire fabric made of 4 mm dia G.I. wire of required width in mesh to concrete/ wooden/ angle iron posts including securing and screwing with 2mm dia G.I. wire, G.I. staples, G.I.U-nails or steel pins etc., complete. Aperture 50x50mm	45.00	sqm	331.00
21	Rocky strata including Boulders. 125 mm dia.	90	Meter	349.00
22	Providing and fixing form work including centring, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for:Columns, beams & walls- circular or any other geometrical shape other than square and rectangular in all sizes	7.68	sqm	356.00

[Handwritten signature]

	PARTICULARS OF ITEMS	Quantity	UOM	Rate
	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.	123.935	Cum	371.00
24	Providing and fixing on wall surface G.I. pipes medium class complete with G.I. fittings and clamps, including cutting, making good the walls etc. and testing of joints complete: 50 mm dia. nominal bore	100	Meter	471.00
25	Providing & laying 60mm thick precast interlocking concrete blocks of approved size (approx 305 sqcm) and shape/ pattern, over 40 mm thick average complete coarse sand bed with joints of 3mm thick filled by fine sand including leveling with surface vibrator, temping	97.75	Sqm	632.00
26	Providing and fixing M.S. clamp of required dia to the top of casing/ housing pipe of tube well as per IS: 2800 (part I), including necessary bolts & nuts of required size complete. 125 mm clamp.	1	Each	1031.00
27	Supplying, assembling, lowering and fixing in vertical position in bore well, ISI marked G.I. casing pipe (Plain) medium class in 4 to 7 meters length one end fitted with socket as per IS: 1239 (Part-1&Part-2) 1992 with IVth revision (Up-to-date amendments), of reputed & approved make, including required hire & labour charges, fittings & accessories, all complete, for all depths, as per direction of Engineer-in-charge. 125 mm nominal dia.	30	Meter	1131.00
28	Carrying out the resistivity survey by VES method using Schlumberger configuration for locating the proper spot for drilling of tube well within the selected habitation, including photography, interpretation of resistivity data and submission of report in the desired format along with resistivity readings, necessary graph and photographs. (only successful point is payable)	1.00	Point	1502.00
29	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).	20.45	Cum	2659.00
30	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 40mm nominal size).	3.075	Cum	3552.00
31	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	6.128	Cum	4073.00

S.N.	PARTICULARS OF ITEMS	Quantity	UOM	Rs.
32	Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	1.47	Cum	4163.00
Electrical SOR 1.06.2020				
33	Supplying, laying and fixing following size submersible cable along with GI/PVC/HDPC pipe line or laid in ground etc as per specification and IS: 694 (2010). Note: Cable should be rust proof, safe from oil / Grease and under water Chemical / abrasion Resistant. 3x2.5 sqmm	87	mtr	64.00
34	Supplying, fixing and cramping suitable size and all type aluminium ferule/ lugs to following size 1.1 KV grade power cable core / lead, pressed with high pressure cramping tool including connection to switch gear/ MCCB etc as per specification. 25 sq. mm	10	Each	22.00
35	Providing and fixing porcelain re-wireable fuse carrier and base unit on wooden board including drilling holes on the board, screws, connections etc. as per specification. (Thimbeling shall be paid separately). 32 amps	6	Each	90.00
36	Providing timber / steel form work for cement concrete work at all levels including removing of the same.	2.54	Cum	103.00
37	Supplying and making end termination with brass compression gland and aluminum lugs for following size armoured aluminum conductor power cable of 1.1 KV grade as per specification. .3 X 35 sq. mm (25 mm)	8	Each	105.00
38	Painting new steel and other metallic surface with red oxide zinc chromide primer paint complete with supply of material labour etc. including preparation of surface.	17.7	Sqm	116.00
39	Painting wood steel and other metallic surface with Aluminium Paint complete with material and labour including preparation of surface.	17.7	Sqm	143.00
40	Supplying and laying following sizes one number FRLS PVC insulated/XLPE, PVC sheathed, steel armoured, aluminium conductor power cable of 1.1 KV grade direct in ground at a depth not less than 40 cm and upto 90 cm including excavation, sand cushioning, protective covering and refilling the trench etc as per specification, IS: 1554 (1988, Part 1) / IS: 7098 (1988, Part 1).	100	Meter	260.00
41	Supplying and fixing G.I. pipe along with wall or pole/ support with 2 Nos MS clamps for protection of under ground cable in approved manner including bolts and nuts or metal dash fasteners complete as per specification. 40 mm dia	100	Meter	359.00

Handwritten signature
SE

	PARTICULARS OF ITEMS	Quantity	UOM	Rate
42	Supplying and fixing water tight terminal box made of 1.6mm thick M.S. sheet with detachable gland plate in bottom, hinged front open able cover, rubber gasket, having 1 Nos 4way connector and 1 No SPMCB inside the box for cable connection, fixed to pole with 2 Nos clamp made from 40x3mm M.S. flat with 2 No nut bolt dully painted with 2 coat of red oxide paint and 2 coat aluminium paint complete as per specification.30x20x15 cms.	3	Each	815.00
43	Supply and fixing following street light pole bracket on existing pole made out of 50 mm dia MS "B" class pipe welded to 300 mm long MS pole canopy of suitable dia at a angle of 102.50 including having MS triangular stiffner of size 150 X 50 X 5 mm thick, making arrangement for tightening the bracket with pole by providing suitable size heavy duty nuts and bolts in canopy, painting with one coat of approved steel primer etc. as per specification.Double Over Hang 1.50 metre Long	8	Each	1869.00
44	Erection of STEEL TUBULAR or "H" BEAM/ ISMB pole in cement concrete 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40 mm nominal size) foundation and cement concrete collar of size 0.4 metre dia and 0.50 metre height from ground level including excavation and refilling etc. as per specification of length:7 metre to 10 metre	3	Each	2610.00
45	Supplying, installation, testing and commissioning of following 230/250 volts LED street light fitting with all accessories like driver, heat sink made of die cast aluminium with IP 66 protection and 15 KV surge protection on pole bracket, including connection, earthing, Separate housing for driver etc complete as per specification and P.F. should be greater than 0.9. LED chip efficacy ratio \geq 120 lumens /watt.45 watt	6	Each	2729.00
46	Providing and laying Cast-in-situ cement concrete 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40mm including mixing with mechanical mixer, compacting with vibrator, finishing and currying etc. complete but excluding form work.	0.76	Cum	2893.00
47	Earthing with G.I. earth pipe 4.5 metre long, 40 mm dia including accessories, and providing masonry enclosure with cover plate having locking arrangement and watering pipe etc. with charcoal and salt as per specification and IS Code 3043: 1987(R 2016)	3	Set	3243.00

Handwritten signature
SIE

S.N.	PARTICULARS OF ITEMS	Quantity	UOM	Rate
48	Supply, installation, testing and commissioning of 1-3 HP 1 phase submersible motor starter cum control wall/ floor mounted type made out of not less than 1.6 mm thick MS sheet and comprising of following panel mounting switchgears there in including connection inter-connection etc. as per specification. a) Phase indicating lamps with fuses and toggle switches 1 set b) 1/2/3 HP 1 phase DOL starter with over load and no volt relay 1 No c) 25 A "C" curve DPMCB 1 No d) Voltmeter 0-250 V 1 set	1	Set	4030.00
49	Supply of swaged steel tubular pole as per IS 2713 with base plate of size 300x300x6mm welded at bottom, necessary hole for cable entry and earthing stud welded at specified height including painting with one coat of red oxide zinc chromate primer.Designation 410 SP-26 height 9.00 metre	3	Each	7168.00
50	Supplying, installation, testing and commissioning of submersible pump set for water supply system with submersible motor directly coupled to multi-stage submersible pump of specified discharge capacity, head, delivery size in existing bore well including 2 sets of suitable size holding clamps made out of 50 mm X 6 mm MS flat, connection with suitable submersible cable of standard length etc. as per specification and IS: 694 (2010). Note: submersible Cable should be rust proof, safe from oil / Grease and under water Chemical / abrasion Resistant..2.0 HP, single phase	1	Set	19805.00
51	AS PER PWD ROAD SOR 01.01.2015 Cement art Mural work	14.25	sqm	3500.00
52	NON SOR ITEM Providing & Planting well developed succulent healthy orna mental plants with digging chemical treatment like thuja, cycas, lolina etc, including 6th month maintenance till well established as directed Engineer In charge	24	Each	550.00
53	NON SOR ITEM Providing & Planting well developed & healthy (5' and above) orna mental plants with digging holes soil filling & chemical & biological treatment like ficus cycas chhatim, bottle palm, supari palm, musanda & avenue palm, tree including 6th month maintenance till well established as directed Engineer In charge	15	Each	970.00
54	NON SOR ITEM Providing & fixing of Steel Bench Area 1.20x0.70 m Height 0.45 m above level seating ----- proper grip fixing with 1:2:4 Cement Concrete	3	Each	9000.00
55	NON SOR ITEM Providing & fixing of Double Swing Jhula	1	Each	19000.00

PARTICULARS OF ITEMS		Quantity	UOM	Rate
NON SOR ITEM				
6	Providing & Planting well established flowering & orna mental plants or shrubs like nerium, bougainvillia, crotons, vidhya etc. with digging holes & chemical treatment including 6th month maintenance till well established as directed Engineer In charge	20	Each	65.00

कार्यपालन अभियन्ता
नगर पालिक निगम, भिलाई

सहायक अभियन्ता
नगर पालिक निगम, भिलाई

उप अभियन्ता
नगर पालिक निगम, भिलाई