

MUNICIPAL CORPORATION OF BHILAI

NIT

वार्ड 30 बालाजी नगर स्थित निर्मला रानी विद्यालय के समीप बैडमिंटन कोर्ट निर्माण कार्य।

(As Per PWD Building SOR 01.01.2015 & NON SOR ITEM)

S.N.	PARTICULERS OF ITEMS	Quantity	UOM	Rate
1	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits.(In all types of soils.)	4.74	cum	
2	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).	2.13	cum	
3	providing and fixing form work including centring, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for: Suspended floors, roofs, access platform, balconies (plain surfaces) and shelves (cast in situ)	7.11	sqm	
4	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	23.28	cum	
	NON SOR			
5	Backed by rich industrial experience and exposure in this domain, devotedly involved in presenting wide assortment of 25mm Artificial Grass.Captivating design Vivacious colors Beautiful pattern	124.00	sqm	
6	LED MODULE 300watts (2year warranty) housing,blacksilver (bajab,havels etc.) AC90-350V,50/60HZ,PFC>0.95,100-135LM/W CRI>75,2700-6500K,IP67,427X305X122mm	4	Each	



Executive Engineer
Municipal Corporation
Bhilai



Assistant Engineer
Municipal Corporation
Bhilai



Sub-Engineer
Municipal Corporation
Bhilai