



**MUNICIPAL CORPORATION BHILAI (C.G.)**  
**NIT**

**Name of work :-** वार्ड कं. 64 सेक्टर 10 सड़क 31ए में पेवर ब्लाक लगाने का कार्य।

S.No.	Description and details of work	Qty.	unit
1	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal	189.2	cum
2	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.	33.11	cum
3	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.	94.6	cum
4	Providing & laying 60mm thick precast interlocking concrete blocks of approved size (approx 305 sqcm) and shape/ pattern, over 40 mm thick average complete coarse sand bed with joints of 3mm thick filled by fine sand including leveling with surface vibrator, temping and sweeping etc. complete of minimum compressive strength of 250 kg/sq.cm rubble mould	756.8	sqm
5	Carriage by mechanical transport upto 5 km lead: 1.26.1 Earth	150	cum

  
**EXECUTIVE ENGINEER**  
MUNICIPAL CORPORATION  
BHILAI

  
**ASSISTANT ENGINEER**  
MUNICIPAL CORPORATION  
BHILAI

  
**Sub Engineer**  
Municipal Corporation  
Bhilai (C.G.)